F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VAR.	2009-020 PP	MCHENRY	25	3
FED. ROAD DIST. NO. 1	ILLINOIS	HIGHWAY PROJECT		

CONTRACT NO. 60G19

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	TOTAL QUANTITIES	CONSTRUCTION TYPE CODE: URBAN 100% FED I000-2A					
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	5	5					
40600300	AGGREGATE (PRIME COAT)	TON	21	21					
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	31	31					
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	411	411					
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	1151	1151					
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	10,275	10,275					
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	3					
67100100	MOBILIZATION	L SUM	1	1					
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	8846	8846					
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	2949	2949					
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	200	200					
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	48648	48648					
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1000	1000					
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	100	100					
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	200	200					
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	365	365					
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	365	365					
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	200	200					
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	574	574					
⊙ Z0076600	TRAINEES	HOUR	500	500					

1

1

CODE NO	ITEM	UNIT	TOTAL QUANTITIES	CONSTRUCTION TYPE CODE: I000-2A					

* SPECIALTY ITEM

⊙ Y080 (100% FEDERAL)

1 Rev. 4-9-09

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

PLOT DATE: 2/5/2009

2/5/2009 pgbrow wgcs:$PWIDOT$$IL$GREENDP$60125047$Design.dgn