ROUTE: Rt 34 form Belmont to Rt 59

CROSS STREETS FROM	CROSS STREETS TO	DIRECTION (EB/WB) (NB/SB)	LANE NO. (1, 2, 3)	PAVEMENT PATCH WIDTH	PAVEMENT PATCH LENGTH	REPAIR AREA (SQ FT)	REPAIR AREA (SQ YD)
Belmont Ave / downwers Gr.		WB	1,2	22	10	220	24
		EB	1,2	10	10	100	11
		EB	1,2	5	10	50	6
		EB / WB	1,2	44	10	440	49
		EB / WB	1,2	44	18	792	88
		EB / WB	1,2	44	22	968	108
		EB / WB	1,2	44	15	660	73
		EB / WB	1,2	44	20	880	98
		EB	1,2	22	30	660	73
		WB	1,2	24	30	720	80
		WB	1,2	22	20	440	49
		EB	1,2	22	22	484	54
		WB / EB	1,2	22	24	528	59
		+ Median	1,2,3,	66	30	1980	220
		WB / EB	1,2	44	50	2200	244
		EB	1,2	22	40	880	98
		WB / EB	1,2	44	40	1760	196
	Cross St	WB / EB	1,2	50	40	2000	222
Cross st		WB / EB	1,2	44	22	968	108
		EB / WB	!,2	22	20	440	49
		WB / EB	1,2	44	20	880	98
		WB / EB	1,2,3	66	40	2640	293
		EB	1,2	22	40	880	98
		WB	1,2	22	40	880	98
		EB	1,2	22	42	924	103
	I- 355	EB / WB	1,2	44	40	1760	196
I- 355		WB / EB	1,2	66	8	528	59
		EB / WB	!,2	66	8	528	59
		WB / EB	1,2	66	8	528	59
		WB / EB	1,2,3	66	6	396	44
		EB	1,2	66	6	396	44
		WB	1,2	66	6	396	44
		EB	1,2	44	10	440	49
		EB / WB	1,2	24	10	240	27
		WB / EB	1,2	44	10	440	49
		WB	1,2	22	10	220	24
		EB	1,2	22	10	220	24
		EB	1,2	22	10	220	24
		EB	1,2	22	10	220	24
		wB	1,2	22	8	176	20
		EB	1,2	22	8	176	20
		EB	1,2	22	10	220	24
		EB	1,2	22	10	220	24
		EB / wB	1,2	44	12	528	59
		WB	1	11	10	110	12
		EB	1,2	22	12	264	29
		WB	1,2	22	12	264	29
		EB	1,2,3	33	10	330	37
	Naperville / Wheaton Rd	WB / EB	1,2	66	10	660	73
Naperville / Wheaton Rd		EB	1,2	22	10	220	24
		WB / EB	1,2,3	66	10	660	73
		EB	1,2	22	6	132	15
		EB / WB	1,2,3	66	6	396	44
		EB	1,2	22	6	132	15

ROUTE: Rt 34 form Belmont to Rt 59

CROSS STREETS FROM	CROSS STREETS TO	DIRECTION (EB/WB) (NB/SB)	LANE NO. (1, 2, 3)	PAVEMENT PATCH WIDTH	PAVEMENT PATCH LENGTH	REPAIR AREA (SQ FT)	REPAIR AREA (SQ YD)
		EB	1,2	22	4	88	10
		EB	1,2	22	4	88	10
		WB	1,2	22	4	88	10
		WB	1,2	22	4	88	10
		EB	1,2	22	4	88	10
		WB	1,2	22	6	132	15
		WB	1,2	22	4	88	10
		EB / WB	1,2	44	6	264	29
		WB	1,2	22	4	88	10
		EB	1,2	22	4	88	10
		WB	1,2	22	6	132	15
		WB / EB	1,2	44	6	264	29
		WB / EB	1,2	44	4	176	20
		EB / WB	1,3	66	4	264	29
		EB	1,2	22	4	88	10
		EB / WB	1,3	66	4	264	29
		EB	1,2	22	6	132	15
		EB	1,2	22	6	132	15
		EB	1,2	22	6	132	15
		EB / WB	1,2	44	4	176	20
	Washington Ave	WB / EB	1,2	44	4	176	20
	Raynond Ave	NB	2	11	200	2200	244
		SB	1,2	22	6	132	15
		NB / SB	1,2	44	6	264	29
		NB / SB	1,3	33	60	1980	220
	300 feet north of Aurora Ave	LT	1,3	12	60	720	80
300 feet north of Aurora Ave		WB	1,2	24	100	2400	267
		WB / EB	1,2	44	100	4400	489
		wB	1,2	24	60	1440	160
		WB	1,2	24	100	2400	267
		EB	1,2,3	24	100	2400	267
		WB / EB	1,2,3	66	90	5940	660
	Median Included	WB / EB	1,2,3	66	100	6600	733
		WB / EB	1,2,3	66	100	6600	733
		WB / EB	1,2,3	66	200	13200	1467
		WB / EB	1,2,3	66	50	3300	367
		WB / EB	1,2,3	66	60	3960	440
		WB / EB	1,2,3	66	90	5940	660
Median Included	Shandrew Dr	WB / EB	1,2,3	66	80	5280	587
		TOTALS			2617 FT		11843 SY

FILE NAME = c:\pw_work\pwidot\smithkl\d0125057\Desig\.dgn	USER NAME = smithkl	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 103.7051 ' / IN.	CHECKED -	REVISED -
	PLOT DATE = 2/5/2009	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

PATCHING SCHEDULE
US 34

SCALE: | SHEET NO. OF SHEETS | STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VAR.	2009-021 PP	DUPAGE	32	6

CONTRACT NO. 60C20

FED. ROAD DIST. NO. 1 | ILLINOIS | FED. AID PROJECT