

ROUTE: IL 53 (IL 56 To I-88)

FROM	TO	DIRECTION (EB/WB) (NB/SB)	LANE NO. (1, 2, 3)	PAVEMENT PATCH WIDTH	PAVEMENT PATCH LENGTH	REPAIR AREA (SQ FT)	REPAIR AREA (SQ YD)
IL 56	I-88	NB	1	12	7	84	9
		NB	2	12	7	84	9
		NB	1	12	7	84	9
		NB	2	12	7	84	9
		NB	CL	2	40	80	9
		NB	1	12	6	72	8
		NB	2	12	6	72	8
		NB	1	12	6	72	8
		NB	2	12	6	72	8
		NB	1	12	6	72	8
		NB	2	12	6	72	8
		NB	1	12	6	72	8
		NB	2	12	6	72	8
		NB	2	12	6	72	8
		NB	2	12	6	72	8
		NB	2	12	6	72	8
		NB	1	12	6	72	8
		NB	Con. Jt.	2	95	190	21
		NB	1	12	6	72	8
		NB	*	12	6	72	8
		NB	*	12	6	72	8
		NB	*	12	6	72	8
		NB	*	12	6	72	8
		NB	*	12	6	72	8
		NB	*	12	6	72	8
		NB	*	12	6	72	8
		NB	*	12	6	72	8
		NB	*	12	6	72	8
		NB	*	12	6	72	8
		NB	*	12	6	72	8
		NB	*	12	6	72	8
		NB	2	12	6	72	8
		NB	1	12	6	72	8
		NB	1	12	6	72	8
		SB	2	12	6	72	8
		SB	2	12	4	48	5
		SB	2	12	4	48	5
		SB	2	12	6	72	8
		SB	1	12	5	60	7
		SB	1	12	4	48	5
		SB	*	12	6	72	8
		SB	*	12	70	840	93
		SB	*	12	6	72	8
		SB	*	12	50	600	67
		SB	*	12	6	72	8
		SB	*	12	3	36	4
		SB	*	12	6	72	8
		SB	*	12	6	72	8
		SB	*	12	12	144	16
		SB	CL	2	50	100	11
		SB	Con. Jt.	4	90	360	40
		SB	2	12	6	72	8
		SB	CL	2	60	120	13
		SB	1	12	25	300	33
		SB	1	12	7	84	9
		SB	2	12	7	84	9
		SB	CL	3	40	120	13
		SB	1	12	4	48	5
		SB	1	12	4	48	5
		SB	CL	3	60	180	20

TOTALS: 866 FT 701 SY

FILE NAME =	USER NAME = amsthk1	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	PATCHING SCHEDULE IL 53			F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
cd:\pw_work\pwrtdot\amsthk1\cd0125857\Design	DRAWN -	REVISED -	VAR.					2009-021 PP	DUPAGE	32	9		
PLOT SCALE = 1/32" = 103.7851' / IN.	CHECKED -	REVISED -	SCALE:			SHEET NO.	OF	SHEETS	STA.	TO STA.	CONTRACT NO. 60G20		
PLOT DATE = 2/5/2009	DATE -	REVISED -	FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT										