F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VAR.	2009-022 PP	WILL	41	3
FED. ROAD DIST. NO. 1	ILLINOIS	HIGHWAY PROJECT		

CONTRACT NO. 60G21

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	TOTAL QUANTITIES	CONSTRUCTION TYPE CODE: URBAN 100% FED I000-2A					
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	27	27					
40600300	AGGREGATE (PRIME COAT)	TON	134	134					
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	201	201					
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	2679	2679					
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	7500	7500					
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	66,963	66,963					
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6					
67100100	MOBILIZATION	L SUM	1	1					
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	30273	30273					
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	10091	10091					
78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	500	500					
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	166500	166500					
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	2000	2000					
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	1000	1000					
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	300	300					
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	2024	2024					
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	2024	2024					
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	1100	1100					
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	1285	1285					
⊙ 20076600	TRAINEES	HOUR	500	500					

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	TOTAL QUANTITIES	CONSTRUCTION TYPE CODE: I000-2A					

* SPECIALTY ITEM

⊙ Y080 (100% FED)

Rev. 4-9-09

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

PLOT DATE: 2/5/2009

2/5/2009
pdm w:\pdm\1001\wil_greendp\60g21\2009pp022\sq1.dgn