

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		URBAN 100% FED 1000-2A				
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	10	10				
40600300	AGGREGATE (PRIME COAT)	TON	50	50				
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	74	74				
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	983	983				
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	2753	2753				
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SO YD	24575	24575				
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6				
67100100	MOBILIZATION	L SUM	1	1				
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	10298	10298				
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	3433	3433				
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	250	250				
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	56635	56635				
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	300	300				
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	200	200				
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	200	200				
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	1475	1475				
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	1475	1475				
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	500	500				
X0322256	TEMPORARY INFORMATION SIGNING	SO FT	463	463				
20076600	TRAINEES	Hour	500	500				

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		1000-2A				

* SPECIALTY ITEM
07080

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES

PLOT DATE: 2/5/2009