

CONTRACT NO. 60G23

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		URBAN 100% FED 1000-2A				
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	19	19				
40600300	AGGREGATE (PRIME COAT)	TON	91	91				
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	136	136				
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	1807	1807				
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	5058	5058				
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SO YD	45156	45156				
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6				
67100100	MOBILIZATION	L SUM	1	1				
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	10091	10091				
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	3364	3364				
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	140	140				
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	55500	55500				
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	800	800				
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	150	150				
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	150	150				
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	850	850				
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	850	850				
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	1300	1300				
X0322256	TEMPORARY INFORMATION SIGNING	SO FT	1131	1131				
Ⓞ 20076600	TRAINEES	HOUR	1500	1500				

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT						

\* SPECIALTY ITEMS

Ⓞ 4080

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

PLOT DATE: 2/9/2009