

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VAR.	2009-025 PP	COOK	49	3
FED. ROAD DIST. NO. 1	ILLINOIS	HIGHWAY PROJECT		

CONTRACT NO. 60G24

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	URBAN 100% FED 1000-2A			
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	32	32			
40600300	AGGREGATE (PRIME COAT)	TON	160	160			
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	240	240			
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	3188	3188			
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	8925	8925			
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SO YD	79,686	79,686			
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6			
67100100	MOBILIZATION	L SUM	1	1			
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	29873	29873			
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	9958	9958			
*78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	350	350			
*78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	164300	164300			
*78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	2400	2400			
*78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	500	500			
*78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	400	400			
*78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	2500	2500			
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	2500	2500			
*88600600	DETECTOR LOOP REPLACEMENT	FOOT	2000	2000			
X0322256	TEMPORARY INFORMATION SIGNING	SO FT	1542	1542			
20076600	TRAINEES	HOLIR	1500	1500			

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES				

* SPECIALTY ITEMS

© Y080

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

Rev. 4-9-09

PLOT DATE: 2/9/2009