

SUMMARY OF QUANTITIES

CODE #	ITEM	UNIT	TOTAL QUANTITY	EASTBOUND MAINLINE ROADWAY 1000	EASTBOUND RAMP ROADWAY 1000	WESTBOUND MAINLINE ROADWAY 1000	WESTBOUND RAMP ROADWAY 1000	EASTBOUND RAMP STRUCTURES 1000	WESTBOUND RAMP STRUCTURES 1000
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	47		47				
20101000	TEMPORARY FENCE	FOOT	1322		753		569		
* 20101100	TREE TRUNK PROTECTION	EACH	21		9		12		
20200100	EARTH EXCAVATION	CU YD	11033	1442	7291	1379	921		
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	4737	475	2892	532	838		
20700110	POROUS GRANULAR EMBANKMENT	TON	2447					1142	1305
20700420	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU YD	3788	475	1943	532	838		
20800150	TRENCH BACKFILL	CU YD	619	278	272	66	3		
20900410	SAND BACKFILL	CU YD	991	826	49	68	48		
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	3230		3230				
* 21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	4950		3318		1632		
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	92		62		30		
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	92		62		30		
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	92		62		30		
NP 25000750	MOWING	ACRE	1		0.7		0.3		
* 25100630	EROSION CONTROL BLANKET	SQ YD	649		649				
* 25200110	SODDING, SALT TOLERANT	SQ YD	4949		3318		1631		
* 25200200	SUPPLEMENTAL WATERING	UNIT	74		50		24		
* 25300600	TRANSPLANTED SALVAGED TREES	EACH	15		15				
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	102		68		34		
28000400	PERIMETER EROSION BARRIER	FOOT	684				684		
28000510	INLET FILTERS	EACH	87	22	30	26	9		
31101200	SUB-BASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	876		486		390		
31200500	STABILIZED SUBBASE HOT-MIX ASPHALT, 4"	SQ YD	56				56		
35300500	PORTLAND CEMENT CONCRETE BASE COURSE 10"	SQ YD	6254	92	5024		1138		
35400500	PORTLAND CEMENT CONCRETE BASE COURSE WIDENING 10"	SQ YD	287	128	89		69		
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	26	3	15	3	.5		
40600215	POLYMERIZED BITUMINOUS MATERIALS (PRIME COAT)	TON	1	1					
40600300	AGGREGATE (PRIME COAT)	TON	7	7					
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	72	36	20		16		
40600990	TEMPORARY RAMP	SQ YD	84	48	20		16		
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	17			14	3		
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	1444	162	815	181	286		
40603315	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N70	TON	155	90	22	43			
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	992	97	549	108	238		

NP = Non-participating

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
 I-90/94 KENNEDY EXPRESSWAY
 STA. TO STA.
 SCALE : 1" = NTS
 DATE : 02/27/09
 DRAWN BY : BEC
 CHECKED BY : GB

PLAN SURVEYED BY DATE
 DATE: _____
 BY: _____
 CHECKED BY: _____
 DATE: _____
 NO. _____

PROFILE SURVEYED BY DATE
 DATE: _____
 BY: _____
 CHECKED BY: _____
 DATE: _____
 NO. _____