

**SUMMARY OF QUANTITIES**

CODE #	ITEM	UNIT	TOTAL QUANTITY	EASTBOUND MAINLINE ROADWAY 1000	EASTBOUND RAMP ROADWAY 1000	WESTBOUND MAINLINE ROADWAY 1000	WESTBOUND RAMP ROADWAY 1000	EASTBOUND RAMP STRUCTURES 1000	WESTBOUND RAMP STRUCTURES 1000	RETAINING WALL 1000
40603600	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N105	TON	380	380						
42000416	PORTLAND CEMENT CONCRETE PAVEMENT 9 3/4" (JOINTED)	SQ YD	56				56			
42001165	BRIDGE APPROACH PAVEMENT	SQ YD	247		126		121			
42101300	PROTECTIVE COAT	SQ YD	8330	1673	3249	1630	1778			
42001420	BRIDGE APPROACH PAVEMENT CONNECTOR (PCC)	SQ YD	49		25		24			
44000100	PAVEMENT REMOVAL	SQ YD	6743		4529		2214			
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	1750		672	328	750			
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	3389	3389						
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	11936	2531	4113	2493	2799			
44002216	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 4"	SQ YD	74			63	11			
44004250	PAVED SHOULDER REMOVAL	SQ YD	8475	2261	2211	2288	1715			
44201765	CLASS D PATCHES, TYPE II 10 INCH	SQ YD	9				9			
44201769	CLASS D PATCHES, TYPE III 10 INCH	SQ YD	21			21				
44201771	CLASS D PATCHES, TYPE IV 10 INCH	SQ YD	36			36				
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	3545	2460	508		577			
48203021	HOT-MIX ASPHALT SHOULDERS, 6"	SQ YD	820		486		334			
48203037	HOT-MIX ASPHALT SHOULDERS, 10"	SQ YD	4903	1891	960	1326	726			
50100300	REMOVAL OF EXISTING STRUCTURES NO. 1	EACH	1						1	
50100400	REMOVAL OF EXISTING STRUCTURES NO. 2	EACH	1					1		
50100500	REMOVAL OF EXISTING STRUCTURES NO. 3	EACH	1						1	
50100600	REMOVAL OF EXISTING STRUCTURES NO. 4	EACH	1					1		
50102400	CONCRETE REMOVAL	CU YD	693					106	132	455
50200100	STRUCTURE EXCAVATION	CU YD	1865							1865
50300225	CONCRETE STRUCTURES	CU YD	1103					88	112	903
50300510	RUSTICATION FINISH	SQ FT	4105							4105
50800105	REINFORCEMENT BARS	POUND	64720							64720
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	48750					14130	18470	16150
51200958	FURNISHING METAL SHELL PILES 14"X0.250"	FOOT	24063							24063
51202305	DRIVING PILES	FOOT	24063							24063
51203200	TEST PILE METAL SHELLS	EACH	4							4
NP 55039700	STORM SEWERS TO BE CLEANED	FOOT	10830	4558	852	3723	1697			
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	69	4		65				
550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	1519	319	1061	139				
550A0360	STORM SEWERS, CLASS A, TYPE 2 15"	FOOT	96		96					
550A0380	STORM SEWERS, CLASS A, TYPE 2 18"	FOOT	37				37			

NP = Non-participating

ILLINOIS DEPARTMENT OF TRANSPORTATION  
**SUMMARY OF QUANTITIES**  
 I-90/94 KENNEDY EXPRESSWAY  
 STA. TO STA.  
 SCALE : 1" = NTS DRAWN BY : BEC  
 DATE : 02/27/09 CHECKED BY : GB

PLAN SURVEYED BY DATE  
 ADJUSTMENT CHECKED  
 R.T. OF WA. CHECKED  
 CAD FILE NAME

PROFILE SURVEYED BY DATE  
 ADJUSTMENT CHECKED  
 R.T. OF WA. CHECKED  
 STRUCTURE NOTATIONS CHECKED