

SUMMARY OF QUANTITIES

CODE #	ITEM	UNIT	URBAN TOTAL QUANTITY	EASTBOUND MAINLINE ROADWAY 1000	EASTBOUND RAMPS ROADWAY 1000	WESTBOUND MAINLINE ROADWAY 1000	WESTBOUND RAMPS ROADWAY 1000										SURVEILLANCE 1000	RETAINING WALL 1000	LIGHTING 1000
* 78003110	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 4"	FOOT	701	467		234													
* 78003120	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 5"	FOOT	1835	939		896													
* 78003130	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 6"	FOOT	70		70														
* 78003140	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 8"	FOOT	4368	3985	383														
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	513	483	30														
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	16		16														
* 78200530	BARRIER WALL MARKERS, TYPE C	EACH	574	156	66	308	44												
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4		4														
78300100	PAVEMENT MARKING REMOVAL	SQ FT	2839	2466		373													
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	440	422	10	4	4												
* 78006937	GROUND ROD, 5/8" DIA. X 10 FT.	EACH	4																4
81000600	CONDUIT IN TRENCH, 2" DIA., GALVANIZED STEEL	FOOT	3026														3026		
81000800	CONDUIT IN TRENCH, 3" DIA., GALVANIZED STEEL	FOOT	687														687		
81001000	CONDUIT IN TRENCH, 4" DIA., GALVANIZED STEEL	FOOT	55														55		
81018600	CONDUIT PUSHED, 2 1/2" DIA., GALVANIZED STEEL	FOOT	100																100
81017515	CONDUIT IN TRENCH, 1 1/4" DIA., COILABLE NONMETALLIC CONDUIT	FOOT	200														200		
81018500	CONDUIT PUSHED, 2" DIA., GALVANIZED STEEL	FOOT	6433														6433		
81018700	CONDUIT PUSHED, 3" DIA., GALVANIZED STEEL	FOOT	3672														3672		
81018900	CONDUIT PUSHED, 4" DIA., GALVANIZED STEEL	FOOT	277														277		
81025400	CONDUIT ENCASED, REINFORCED CONCRETE, 4" DIA., PVC 1 WIDE X 1 HIGH	FOOT	1339														1339		
81100600	CONDUIT ATTACHED TO STRUCTURE, 2" DIA., GALVANIZED STEEL	FOOT	1105														1105		
81100800	CONDUIT ATTACHED TO STRUCTURE, 3" DIA., GALVANIZED STEEL	FOOT	180														180		
* 81200270	CONDUIT EMBEDDED IN STRUCTURE, 4" DIA., PVC	FOOT	3080														3080		
81400200	HEAVY-DUTY HANDHOLE	FOOT	59																
* 80180046	AERIAL CABLE, 3-1C NO. 1/0, ALUMINUM, WITH MESSENGER WIRE	FOOT	1000																1000
83057350	LIGHT POLE, WOOD 60 FT., CLASS 4	EACH	4																4
81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	550																550
84400205	RELOCATE EXISTING LIGHT TOWER	EACH	1																1
A2004816	TREE, GLEDITSIA TRIACANTHOS INERMIS SKYLINE (SKYLINE THORNLESS COMMON HONEYLOCUST), 2" CALIPER, BALLED AND BURLAPPED	EACH	2		2														
X0322923	SEGMENTAL CONCRETE BLOCK WALL	SQ FT	1483		1483														
X0323988	TEMPORARY SOIL RETENTION SYSTEM	SQ FT	3300														3300		
X0324876	CONCRETE BARRIER (SPECIAL)	FOOT	292	192		100													
X6063600	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-4.24	FOOT	3903	50	3379	309	165												
X7011015	TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)	L SUM	1	0.25	0.25	0.25	0.25												

*Specialty Items

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
 I-90/94 KENNEDY EXPRESSWAY
 STA. TO STA.
 SCALE : 1" = NTS DRAWN BY : BEC
 DATE : 02/27/09 CHECKED BY : GB

SURVEYED BY: _____ DATE: _____
 PLAN NO.: _____
 CHECKED BY: _____
 DATE: _____
 REVISIONS: _____
 DATE: _____
 BY: _____

SURVEYED BY: _____ DATE: _____
 PROFILE NO.: _____
 CHECKED BY: _____
 DATE: _____
 REVISIONS: _____
 DATE: _____
 BY: _____