

DRAINAGE SCHEDULE

LOCATION		SS CL A 1	SS CL A 2	SS CL A 2	SS CL A 2	SS DUCTILE IRON 12"	SS JKD CL A 2 18	TRENCH BKFIL	SS CLEAN	CB TA 4 DIA T8G	CB TA 4 DIA T24F&G	MH TA 4 DIA T1F CL	MH TA 5 DIA T1F CL	MH TA 7 DIA T1F CL	INL TB T24F&G	PIPE UNDER DRAINS 4	DRAINAGE STR. CLEANED
ROAD	STATION	12	12	15	18	FOOT	FOOT	CUL. YD.	FOOT	EACH	EACH	EACH	EACH	EACH	EACH	FOOT	EACH
I-90/94 E. B. MAINLINE	20+00 - 35+00	4	137			232	110	229	680		12	3	1		1		8
	35+00 - 50+00		182					49	2120		1				1		12
	50+00 - 65+00								1758								24
	65+00 - 80+00																
	SUBTOTAL	4	319			232	110	278	4558		13	3	1		3		44
I-90/94 E. B. RAMPS	20+00 - 35+00		395	96				159	425	1	3	1	1		2	640	6
	35+00 - 50+00		666					113	203	2	6	5	1		4	884	9
	50+00 - 65+00								224								8
	65+00 - 80+00																
	SUBTOTAL		1061	96				272	852	3	9	6	2		6	1524	23
I-90/94 W. B. MAINLINE	20+00 - 35+00	54	56			12		49	1477	1	6	1		1	2		7
	35+00 - 50+00		73					13	1493		6						14
	50+00 - 65+00	11	10					4	753		2						10
	65+00 - 80+00																
	SUBTOTAL	13	139			12		66	3723	1	14	1		1	2		31
I-90/94 W. B. RAMPS	20+00 - 35+00				37			3	1171								15
	35+00 - 50+00								426								12
	50+00 - 65+00								100								7
	65+00 - 80+00																
	SUBTOTAL				37			3	1697								34
TOTAL		69	1519	96	37	244	110	619	10830	4	36	10	3	1	11	1524	132

DRAINAGE SCHEDULE (CONT.)

LOCATION		CB ADJ	CB ADJ NEW T1F OL	CB ADJ NEW T8G	CB ADJ NEW T24F&G	CB RECON NEW T24F&G	MAN ADJUST	MAN ADJUST T1F CL	MAN RECON	INLETS ADJ	INLETS ADJ NEW T1F OL	INLETS ADJ NEW T24F&G	REMOV MAN	REMOV CB	REMOV INLET	SS REMOV 12
ROAD	STATION	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH
I-90/94 E. B. MAINLINE	20+00 - 35+00	1	1	2		1	2						3	4		146
	35+00 - 50+00		2		1				1			1		1		14
	50+00 - 65+00															
	65+00 - 80+00															
	SUBTOTAL	1	3	2	1	1	2		1			1	3	5		157
I-90/94 E. B. RAMPS	20+00 - 35+00		1								1	1	1	5	3	126
	35+00 - 50+00				1		1		2		2	2	2	5	1	222
	50+00 - 65+00															
	65+00 - 80+00															
	SUBTOTAL		1		1		1		2		1	3	3	10	4	348
I-90/94 W. B. MAINLINE	20+00 - 35+00	3	2										1	2		74
	35+00 - 50+00		2		1			2						3		25
	50+00 - 65+00															4
	65+00 - 80+00															
	SUBTOTAL	3	4		1			2					1	5		103
I-90/94 W. B. RAMPS	20+00 - 35+00			1	1					1				1	2	48
	35+00 - 50+00	1			1		4	1			2				3	
	50+00 - 65+00			1											1	
	65+00 - 80+00															
	SUBTOTAL	1		2	2		4	1		1	2			1	6	48
TOTAL	5	8	4	5	1	7	3	3		1	1	6	7	21	10	659

EROSION CONTROL & LANDSCAPING SCHEDULE

LOCATION		TEMPORARY FENCE	TREE TRUNK	TOPSOIL FURNISH & PLACE 4	NITROGEN FERTILIZER NUTRIENT	PHOSPHORUS FERTILIZER NUTRIENT	POTASSIUM FERTILIZER NUTRIENT	MOWING	EROSION CONTROL BLANKET	SODDING SALT TOLERANT	SUPPLE MENTAL WATERING	TRANSPLANT SALVAGED TREES	TEMPORARY EROSION CONTROL SEEDING	PERIMETER EROSION BARRIER	INLET FILTERS
ROAD	STATION	FOOT	FOOT	SQ. YD.	POUND	POUND	POUND	ACRE	SQ. YD.	SQ. YD.	UNIT	EACH	POUND	FOOT	EACH
I-90/94 E. B. MAINLINE	20+00 - 35+00														16
	35+00 - 50+00														6
	50+00 - 65+00														
	65+00 - 80+00														
	SUBTOTAL														22
I-90/94 E. B. RAMPS	20+00 - 35+00	126	8	776	14	14	14	0.2	649	776	12	3	16		10
	35+00 - 50+00	627	1	2542	47	47	47	0.5		2542	38		53		20
	50+00 - 65+00														
	65+00 - 80+00														
	SUBTOTAL	753	9	3318	62	62	62	0.7	649	3318	50	3	69		30
I-90/94 W. B. MAINLINE	20+00 - 35+00														15
	35+00 - 50+00														6
	50+00 - 65+00														
	65+00 - 80+00														
	SUBTOTAL	0													21
I-90/94 W. B. RAMPS	20+00 - 35+00	569	9	865	16	16	16	0.2		865	13	12	18	530	3
	35+00 - 50+00		3	766	14	14	14	0.2		766	11		16	154	6
	50+00 - 65+00														5
	65+00 - 80+00														
	SUBTOTAL	569	12	1631	30	30	30	0.3		1631	24	12	34	684	14
TOTAL	1322	21	4949	92	92	92	1.0	649	4949	74	15	102	684	87	

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF QUANTITIES
 I-90/94 KENNEDY EXPRESSWAY
 STA. TO STA.
 SCALE : 1" = NTS DRAWN BY : BEC
 DATE : 02/27/09 CHECKED BY : GB

DATE: _____ BY: _____
 PLAN: _____
 REVISIONS:
 1. _____
 2. _____
 3. _____

DATE: _____ BY: _____
 PROFILE: _____
 REVISIONS:
 1. _____
 2. _____
 3. _____