F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	2021.1B-R	COOK	101	009
STA.		TO STA.		
FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT		

CONTRACT NO. 62532

SUMMARY OF QUANTITIES

	CODE NO.	ITEM	UNIT	100% FED URBAN X771-2A TOTAL QUANTITY	ROADWAY	BRIDGE (1)	LIGHTING	CDOT LIGHTING	CDOT TRAFFIC SIGNALS						
					CONSTRUCTION TYPE CODE										
*	X0966700	JUNCTION BOX, POLE OR POST MOUNTED	EACH	10					10						
	X7011015	TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)	L SUM	1	1										
*	X8410102	TEMPORARY LIGHTING SYSTEM	L SUM	1				1							
~~*~~	~~X0323157~~	~~REMOVE LUMINAIRE FROM UNDERPASS~~	~~EACH~~	~~12~~			~~12~~								
	XX104800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-V.12	FOOT	418	418										
	Z0013798	CONSTRUCTION LAYOUT	L SUM	1	0.5	0.5									
□	Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	15	15										
	Z0018800	DRAINAGE SYSTEM	L SUM	1		1									
	Z0018940	DRILL EXISTING MANHOLE OR HANDHOLE	EACH	83				29	54						
	Z0030240	IMPACT ATTENUATOR, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 2	EACH	2	2										
	Z0030250	IMPACT ATTENUATOR, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	4	4										
	Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1										
	Z0064800	SELECTIVE CLEARING	UNIT	1	1										
	Z0073300	TEMPORARY SHORING AND CRIBBING	L SUM	1		1									
⊙	Z0076600	TRAINEES	HOUR	1,000	1,000										
*	81900302	TRENCH AND BACKFILL WITH SCREENINGS OR SAND	FOOT	1232				1232							
*	84200700	LIGHTING FOUNDATION REMOVAL	EACH	3				3							
*	81100805	CONDUIT ATTACHED TO STRUCTURE, 3" DIA., PVC COATED GALVANIZED STEEL	FOOT	940					940						
*	X0326347	ELECTRIC CABLE IN CONDUIT NO. 4 2 C	FOOT	205					205						
*	87301155	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 12 7 C	FOOT	612					612						
*	81702400	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 3-1/C NO. 2	FOOT	150				150							
*	X0322709	CONTROLLER, STREET LIGHTING, BASE MOUNTED, 1-PHASE, 100 AMP	EACH	1				1							
*	X8300100	LIGHT POLE, ALUMINUM, WITH MAST ARM, INSTALL ONLY	EACH	6				6							
*	82107100	UNDERPASS LUMINAIRE, 70 WATT, HIGH PRESSURE SODIUM VAPOR	EACH	12			12								
*	X8210305	PROTECTION AND MAINTENANCE OF EXISTING UNDERPASS LIGHTING	L SUM	1			1								
*	81028080	CONDUIT, BORED AND PULLED, COILABLE NON-METALLIC CONDUIT, 3"	FOOT	948					948						
*	X8210407	LUMINAIRE, INSTALL ONLY	EACH	19			19								
	X0322915	METAL LIGHT POLE, INSTALL ONLY	EACH	10				2	8						
	X0324705	MAST ARM, STEEL, STREET LIGHTING, 12 FOOT, INSTALL ONLY	EACH	12				12							

⊙ Y080
* DENOTES SPECIALTY ITEMS
□ NON-PARTICIPATING

BRIDGE INFORMATION

(1) 111TH ST. OVER NB & SB I-57 S.N. 016-0989

REVISIONS	
NAME	DATE

Rev.

ILLINOIS DEPARTMENT OF TRANSPORTATION
111TH STREET OVER
F.A.I ROUTE 57 (INTERSTATE 57)

SUMMARY OF QUANTITIES

SCALE: N.T.S. DRAWN BY: BRH
DATE: 01/15/09 CHECKED BY: ACL

TENG
TENG & ASSOCIATES, INC.
ENGINEERS/ARCHITECTS/PLANNERS
205 N. MICHIGAN AVE. CHICAGO, IL 60601
TELEPHONE: 312/616-0000