

**BILL OF MATERIALS - TRAFFIC SIGNAL WORK**

DESCRIPTION	UNIT	TOTAL QUANTITY	111TH ST & MARSHFIELD	111TH ST & HAMLET AVE
SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	4	2	2
SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, MAST ARM MOUNTED	EACH	12	7	5
SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 4-SECTION, BRACKET MOUNTED	EACH	2	1	1
SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 4-SECTION, MAST ARM MOUNTED	EACH	2	1	1
PEDESTRIAN SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, BRACKET MOUNTED	EACH	12	6	6
TEMPORARY TRAFFIC SIGNAL INSTALLATION	EACH	2	1	1
ROD AND CLEAN DUCT IN EXISTING CONDUIT SYSTEM	FOOT	1925	1025	900
CONCRETE FOUNDATION FOR TYPE "P" BASE MOUNTED TRAFFIC SIGNAL CONTROLLER	EACH	2	1	1
CONCRETE FOUNDATION 24" DIA.	FOOT	45	27	18
CONCRETE FOUNDATION 30" DIA.	FOOT	22	11	11
STREET NAME SIGN	EACH	7	4	3
REMOVE EXISTING TRAFFIC SIGNAL FOUNDATION	EACH	7	4	3
SOLID STATE FULL-ACTUATED CONTROLLER, 4-PHASE DIGITAL TIMING WITH SOLID STATE TIME BASE COORDINATOR IN BASE MOUNTED CABINET	EACH	2	1	1
PVC CONDUIT IN TRENCH 3" (SCHEDULE #80)	FOOT	112	35	77
PVC CONDUIT IN TRENCH 4" (SCHEDULE #80)	FOOT	151	110	41
MAST ARM, STEEL, MONOTUBE 20 FT.	EACH	3	2	1
MAST ARM, STEEL, MONOTUBE 26 FT.	EACH	2	1	1
MAST ARM, STEEL, MONOTUBE 35 FT.	EACH	2	1	1
ELECTRIC CABLE IN CONDUIT NO. 12 19/C	FOOT	1087	724	363
REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	L SUM	1	0.5	0.5
SIGN, MESSAGE, ELECTRICALLY ILLUMINATED, FIBER OPTIC, MAST ARM MOUNTED	EACH	4	2	2
SIGN, MESSAGE, ELECTRICALLY ILLUMINATED, FIBER OPTIC, BRACKET MOUNTED	EACH	4	2	2
JUNCTION BOX, POLE OR POST MOUNTED	EACH	10	6	4
DRILL EXISTING MANHOLE OR HANDHOLE	EACH	15	8	7
COILABLE CONDUIT INSTALLATION BY DIRECTIONAL BORING	FOOT	948	498	450
PVC CONDUIT ATTACHED TO STRUCTURE 3" (Schedule #80)	FOOT	950	950	-
POLE, CITY, STEEL ANCHOR BASE 10" DIAMETER, 3 GAUGE, 32'-6"	EACH	2	1	1
POLE, CITY, STEEL ANCHOR BASE 10" DIAMETER, 3 GAUGE, 34'-6"	EACH	8	5	3
ELECTRIC CABLE IN CONDUIT NO. 4 2/C	FOOT	195	145	50
ELECTRIC CABLE IN CONDUIT NO. 12 7/C	FOOT	575	575	-
TRENCH AND BACKFILL WITH SCREENING	FOOT	214	117	97

T:\DOCUMENT\19080606\CIVIL\DDN\EXH009\00\DDN  
 111TH ST BORDER.DGN  
 11-16-2009, 12:00:49  
 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30 31 32 33 34 35 36 37 38 39 40 41 42 43 44 45 46 47 48 49 50 51 52 53 54 55 56 57 58 59 60 61 62 63


TS-1

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 111TH STREET OVER  
 F.A.I ROUTE 57 (INTERSTATE 57)  
  
**TRAFFIC SIGNAL**  
**SUMMARY OF QUANTITIES**

SCALE: NONE  
 DATE: 01/16/09

DRAWN BY: ACL  
 CHECKED BY: RMW


 TENGO & ASSOCIATES, INC.  
 ENGINEERS/ARCHITECTS/PLANNERS  
 209 N. MICHIGAN AVE., CHICAGO, IL 60601  
 TELEPHONE: 312.916.0000