

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
360	(54&56) RS-6	KANE/COOK	37	3
FED. ROAD DIST. NO. 1		ILLINOIS	HIGHWAY PROJECT	

SUMMARY OF QUANTITIES			100% FED. URBAN	CONSTRUCTION TYPE CODE			
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	KANE CO. BRIDGE SN 045-0042 SYTY-2A	KANE 1000-2A	COOK 1000-2A	
20200100	EARTH EXCAVATION	CU YD	26		26		
20800150	TRENCH BACKFILL	CU YD	5		5		
21101615	TOPSOIL FURNISH AND PLACE, 4"	SO YD	533		400	133	
21400100	GRADING AND SHAPING DITCHES	FOOT	480		380	100	
25000210	SEEDING, CLASS 2A	ACRE	0.25		0.15	0.1	
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	23		15	8	
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	23		15	8	
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	23		15	8	
NP X0326394	FLOOR DRAINS TO BE CLEANED	EACH	16	16			
25100630	EROSION CONTROL BLANKET	SO YD	533		400	133	
28100105	STONE RIPRAP, CLASS A3	SO YD	34		34		
28200200	FILTER FABRIC	SO YD	34		34		
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	24		22	2	
40600300	AGGREGATE (PRIME COAT)	TON	124		112	12	
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	31		28	3	
40600895	CONSTRUCTING TEST STRIP	EACH	4		2	2	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	102			102	
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SO YD	274		274		
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	1008		997	11	
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	5191		4706	485	
42001300	PROTECTIVE COAT	SO YD	2490		2490		
44000153	HOT-MIX ASPHALT SURFACE REMOVAL, 1"	SO YD	5600		1300	4300	
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SO YD	62923		61223	1700	
X0325984	HOT-MIX ASPHALT MEDIAN SURFACE REMOVAL	SO YD	152		152		
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SO YD	360		360		
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	6000		6000		
44002212	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 3"	SO YD	5942		5344	598	
44002600	GUTTER OUTLET REMOVAL	FOOT	20			20	

SUMMARY OF QUANTITIES			100% FED. URBAN	CONSTRUCTION TYPE CODE			
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	KANE CO. BRIDGE SN 045-0042 SYTY-2A	KANE 1000-2A	COOK 1000-2A	
44003510	MEDIAN REMOVAL PARTIAL DEPTH	SO FT	9138		9138		
44201815	CLASS D PATCHES, TYPE II, 14 INCH	SO YD	3680		3312	368	
44201819	CLASS D PATCHES, TYPE III, 14 INCH	SO YD	288		258	30	
44201821	CLASS D PATCHES, TYPE IV, 14 INCH	SO YD	1974		1774	200	
50300255	CONCRETE SUPERSTRUCTURE	CU YD	42				
50104000	BRIDGE RAIL REMOVAL	FOOT	574		574		
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	8,890		8,890		
50900805	PEDESTRIAN RAILING	FOOT	575		575		
54213681	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 36"	EACH	1		1		
NP 55039700	STORM SEWERS TO BE CLEANED	FOOT	2802		2802		
551A0500	STORM SEWER INSTALLATION, CLASS A 12"	FOOT	20		20		
60210414	CATCH BASINS, TYPE C, SPECIAL, TYPE 24 FRAME AND GRATE	EACH	5		5		
60250200	CATCH BASINS TO BE ADJUSTED	EACH	21		21		
60251740	CATCH BASINS TO BE ADJUSTED WITH NEW TYPE 24 FRAME AND GRATE	EACH	40		40		
60255500	MANHOLES TO BE ADJUSTED	EACH	10		10		
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	4		4		
60600095	CLASS SI CONCRETE (OUTLET)	CU YD	3		3		
60618200	BITUMINOUS MEDIAN SURFACE	SO FT	1368		1368		
* 63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	420		420		
63200310	GUARDRAIL REMOVAL	FOOT	507		507		
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6		6		
67100100	MOBILIZATION	L SUM	1		0.9	0.1	
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1		0.9	0.1	
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1		0.9	0.1	
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1		0.9	0.1	
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	23		23		
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	7280		6465	815	
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	474		401	73	

NP- Non-participating  
\* Specialty Items

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
SUMMARY OF QUANTITIES

2/6/2009 10:48:38 AM C:\WORK\2009\10000155\10000155.dwg