

CODE NUMBER	ITEM	UNIT	Roadway J000-2A		SFTY-3N IMPACT ATTENUATORS	Traffic Signals Y031-1F	HIGHWAY LIGHTING / ITS Y030-1E	Bridge SN 045-3166 X031-2A	Bridge SN 045-3164 X031-2A	Landscaping Y003	TOTAL QUANTITY
			STEARNS ROAD	IL RTE 25							
XX006723	TEMPORARY AGGREGATE BERM-RIPRAP	TON	582								582
XX006727	TEMPORARY DITCH CHECKS, ROLLED EXCELSIOR	FOOT	2,400	100							2,500
XX006821	CONCRETE TRUCK WASHOUT	L SUM	1								1
* XX006937	GROUND ROD, 5/8" DIA. X 10 FT.	EACH					3				3
XX007023	STAINING CONCRETE STRUCTURES	SQ YD	200								200
XX172700	MANHOLES, TYPE A, 8'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1								1
Z0001050	AGGREGATE SUBGRADE 12"	SQ YD	62,488	3,541							66,029
Z0013798	CONSTRUCTION LAYOUT	L SUM	1								1
Z0018000	DRAINAGE SCUPPERS (SPECIAL)	EACH						16			16
Z0018400	DRAINAGE STRUCTURES TO BE ADJUSTED	EACH	6								6
Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	26								26
Z0018800	DRAINAGE SYSTEM	L SUM						1			1
Z0019600	DUST CONTROL WATERING	UNIT	302								302
* Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH			1						1
* Z0030260	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	EACH			1						1
* Z0030330	IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE), TEST LEVEL 3	EACH			1						1
Z0034390	MODULAR EXPANSION JOINT 6"	FOOT						126			126
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1								1
Z0065745	SLOTTED DRAIN 12" WITH 2 1/2" SLOT	FOOT	20								20
Δ Z0076600	TRAINEES	hour	2,640	360							3,000
* <del>XX007878</del>	EROSION CONTROL BLANKET (SPECIAL 1)	SQ YD	22,351								22,351
* <del>XX007879</del>	EROSION CONTROL BLANKET (SPECIAL 2)	SQ YD	12,378								12,378
* <del>XX007880</del>	EROSION CONTROL BLANKET (SPECIAL 3)	SQ YD	16,027								16,027
<del>XX007896</del>	CLEARING (SPECIAL)	TON	200								200
* <del>XX007881</del>	DOCUMENTATION CAMERAS	L SUM	1								1
<del>XX007882</del>	DRAINAGE STRUCTURES TO BE ADJUSTED WITH A NEW TYPE 24 FRAME AND GRATE	EACH	20								20
* <del>XX007883</del>	5" RIGID GALVANIZED STEEL MULTI-DUCT W/ 4 1-1/4" INNER DUCT IN TRENCH	FOOT					1,450				1,450
* <del>XX007884</del>	5" RIGID GALVANIZED STEEL MULTI-DUCT W/ 4 1-1/4" INNER DUCT ATTACHED TO STRUCTURE	FOOT					3,880				3,880
<del>XX007885</del>	ROOFING SYSTEM	FOOT							534		534
* Z0005215	BITUMINOUS STABILIZATION STEEL PLATE BEAM GUARDRAIL	SQ YD	676	165							841
<del>10324775</del>	SEDIMENT CONTROL, STABILIZED CONSTRUCTION ENTRANCE MAINTENANCE	SQ YD	1,744								1,744
<del>XX000306</del>	CLAY LINER	CU FT	76,845								76,845
<del>10320015</del>	SEDIMENT CONTROL, STABILIZED CONSTRUCTION ENTRANCE REMOVAL	EACH	3								3
<del>10322250</del>	TEMPORARY SIGN	SQ FT	213								213

\* Specialty Items

FILE NAME =  
Soq\_070793\_01.SHT.cgn

USER NAME = GTINE  
PLOT SCALE = 1'  
PLOT DATE = 2/12/2009

DESIGNED GT  
DRAWN GT  
CHECKED MCW  
DATE 01/16/09

REVISED - A ADDENDUM 4/9/09  
REVISED -  
REVISED -  
REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
361	06-00214-20-BR	KANE	320	11
CONTRACT NO. 63075				
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				