

CODE NUMBER	ITEM	UNIT	Roadway J000-2A		SFTY-3N IMPACT ATTENUATORS	Traffic Signals Y031-1F	HIGHWAY LIGHTING / ITS Y030-1E	Bridge SN 045-3166 X031-2A	Bridge SN 045-3164 X031-2A	Landscaping Y003	TOTAL QUANTITY
			STEARNS ROAD	IL RTE 25							
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON		295							295
40600895	CONSTRUCTING TEST STRIP	EACH		1							1
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD		160							160
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	1,259	2,147							3,406
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	471	101							572
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	240	795							1,035
42000501	PORTLAND CEMENT CONCRETE PAVEMENT 10" (JOINTED)	SQ YD	44,584								44,584
42001185	BRIDGE APPROACH PAVEMENT	SQ YD	658								658
42001300	PROTECTIVE COAT	SQ YD	59,864	43			7,137	671			67,715
42001400	BRIDGE APPROACH PAVEMENT (SPECIAL)	SQ YD	287								287
42001420	BRIDGE APPROACH PAVEMENT CONNECTOR (PCC)	SQ YD	2,150								2,150
44000100	PAVEMENT REMOVAL	SQ YD		215							215
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD		3,515							3,515
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD		227							227
44004250	PAVED SHOULDER REMOVAL	SQ YD		963							963
44201798	CLASS D PATCHES, TYPE I, 13 INCH	SQ YD		80							80
44201803	CLASS D PATCHES, TYPE II, 13 INCH	SQ YD		80							80
44201807	CLASS D PATCHES, TYPE III, 13 INCH	SQ YD		240							240
44201809	CLASS D PATCHES, TYPE IV, 13 INCH	SQ YD		400							400
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT		2,508							2,508
48101200	AGGREGATE SHOULDERS, TYPE B	TON	38	301							339
48203021	HOT-MIX ASPHALT SHOULDERS, 6"	SQ YD	108	1,241							1,349
50105220	PIPE CULVERT REMOVAL	FOOT	36	265							301
50200100	STRUCTURE EXCAVATION	CU YD	2,230				1,815	44			4,089
50200300	COFFERDAM EXCAVATION	CU YD					764				764
50200500	COFFERDAMS	EACH					2				2
50300225	CONCRETE STRUCTURES	CU YD	36				2,003	104			2,143
50300255	CONCRETE SUPERSTRUCTURE	CU YD					1,839	32			1,871
50300260	BRIDGE DECK GROOVING	SQ YD					6,071	670			6,741
50300265	SEAL COAT CONCRETE	CU YD					247				247
50300280	CONCRETE ENCASEMENT	CU YD					32	1			33
50300285	FORM LINER TEXTURED SURFACE	SQ FT					18,203				18,203
50400205	PRECAST PRESTRESSED CONCRETE DECK BEAMS (11" DEPTH)	SQ FT						4,885			4,885
50500505	STUD SHEAR CONNECTORS	EACH					16,800	429			17,229
50800105	REINFORCEMENT BARS	POUND	40,100				185,370	32,800			258,270
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	2,200				879,950	75,960			958,110
50800515	BAR SPLICERS	EACH					122	39			161

* Specialty Items

FILE NAME =
Soq_070793_01.SHT.dgn

USER NAME = GTINE

DESIGNED GT

REVISED -

DRAWN GT

REVISED -

PLOT SCALE = 1"

CHECKED MCW

REVISED -

PLOT DATE = 2/13/2009

DATE 01/16/09

REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: N/A SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
361	06-00214-20-BR	KANE	320	5
CONTRACT NO. 63075				
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				