

F. A. U. REC.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
348	07-00055-00-LS	COOK	41	3
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

CONTRACT #63106

SUMMARY OF QUANTITIES					Chicago Ridge	Palos Hills	Bridgeview	Bedford Park	Worth	Burbank	Oak Lawn
S.I.	CODE NO.	PAY ITEM	UNIT	QUAN	CONSTRUCTION TYPE CODE						
					Y003	Y003	Y003	Y003	Y003	Y003	Y003
	20100110	TREE REMOVAL (6 TO 15 UNIT DIAMETER)	UNIT	34				34			
	20100210	TREE REMOVAL (OVER 15 UNIT DIAMETER)	UNIT	15				15			
	20200100	EARTH EXCAVATION	CU YD	730				730			
	20400800	FURNISHED EXCAVATION	CU YD	2000				1770	230		
	21101625	TOPSOIL FURNISH AND PLACE, 6"	SQ YD	4970				4400	570		
	21101625	TOPSOIL FURNISH AND PLACE, 24"	SQ YD	4000				4000			
	21101810	COMPOST FURNISH AND PLACE, 3"	SQ YD	10125				8425	1700		
*	25000110	SEEDING, CLASS 1A	ACRE	1.85	0.03			1.77		0.05	
*	25000115	SEEDING, CLASS 1B	ACRE	1.3				1.3			
*	25200200	SUPPLEMENTAL WATERING	UNIT	179	5			150	20	1	2
*	25003110	INTERSEEDING, CLASS 1A	ACRE	1.2	0.15	0.05		0.7	0.2	0.05	0.05
*	25100630	EROSION CONTROL BLANKET	SQ YD	22975	145			21000	1600	230	
	31101200	SUB-BASE GRANULAR MATERIAL, TYPE B, 4"	SQ YD	10418	101	261		9436	620		
	42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6"	SQ YD	811	811						
	42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5"	SQ FT	95740	903	2342		86923	5572		
	42400800	DETECTABLE WARNING	SQ FT	496	8	8		464	16		
	44000100	PAVEMENT REMOVAL	SQ YD	4352	158			4194			
	44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	811	811						
	44000300	CURB REMOVAL	FOOT	363	9			354			
	44000600	SIDEWALK REMOVAL	SQ FT	902	838			64			
	44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	1083		28		1035	20		
	44001900	COMBINATION CONCRETE CURB AND GUTTER REMOVAL (SPECIAL)	FOOT	9365		25		9340			
	44003800	MEDIAN SURFACE REMOVAL	SQ FT	41750				41750			
	44003100	MEDIAN REMOVAL	SQ FT	278				278			
	48203021	HOT-MIX SHOULDERS, 6 INCH	SQ YD	310				310			
	54213669	PRECAST REINFORCED CONCRETE FLARED END SECTION, 24 INCH	EACH	1				1			
	550A0050	STORM SEWER, CLASS A, TYPE 1, 12"	FOOT	27				27			
	550A0090	STORM SEWER, CLASS A, TYPE 1, 18"	FOOT	85				85			
	550A0120	STORM SEWER, CLASS A, TYPE 1, 24"	FOOT	353				353			
	60207605	CATCH BASIN, TYPE C., TYPE B GRATE	EACH	2				2			
	60218400	MANHOLES, TYPE A, 4' DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1				1			
	60250200	CATCH BASINS TO BE ADJUSTED	EACH	19				19			
	60255500	MANHOLES TO BE ADJUSTED	EACH	16				16			
	60265700	VALVE VAULTS TO BE ADJUSTED	EACH	4				4			
	60500050	REMOVING CATCH BASINS	EACH	2				2			
	60600605	CONCRETE CURB, TYPE B	FOOT	10170	56	25		10089			
	60619200	CONCRETE MEDIAN, TYPE SB-6.06	SQ FT	278				278			
*	63000003	STEEL PLATE BEAM GUARD RAIL, TYPE A, 9 FOOT POSTS	FOOT	438				250	188		
*	63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	1				1			
*	63100070	TRAFFIC BARRIER TERMINAL, TYPE 5	EACH	1				1			
*	63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	1				1			
*	63100167	TRAFFIC BARRIER TERMINAL, TYPE 1, SPECIAL (TANGENT)	EACH	1				1			
	63200310	GUARDRAIL REMOVAL	FOOT	538				263	275		
	67100100	MOBILIZATION	L. SUM	1	0.11	0.03		0.72	0.07	0.03	0.04
	70102630	TRAFFIC CONTROL AND PROTECTION STANDARD 701601	L. SUM	1	0.11	0.03		0.72	0.07	0.03	0.04
	70102635	TRAFFIC CONTROL AND PROTECTION STANDARD 701701	L. SUM	1	0.11	0.03		0.72	0.07	0.03	0.04
	70102640	TRAFFIC CONTROL AND PROTECTION STANDARD 701801	L. SUM	1	0.11	0.03		0.72	0.07	0.03	0.04
	81400115	HANDHOLE TO BE ADJUSTED	EACH	15				15			
*	A2000118	TREE, ACER X FREEMANII AUTUMN BLAZE (AUTUMN BLAZE FREEMAN MAPLE), 3" CALIPER, BALLED AND BURLAPPED	EACH	80				55		4	21
*	A2002470	TREE, BETULA NIGRA HERITAGE (HERITAGE RIVER BIRCH), 8' HEIGHT, CLUMP FORM, BALLED AND BURLAPPED	EACH	15				9			
*	A2002476	TREE, BETULA NIGRA HERITAGE (HERITAGE RIVER BIRCH), 12' HEIGHT, CLUMP FORM, BALLED AND BURLAPPED	EACH	50				34	16		
*	A2004824	TREE, GLEDITSIA TRIACANTHOS INERMIS SKYLINE (SKYLINE THORNLESS COMMON HONEYLOCUST) 3" CALIPER, BALLED AND BURLAPPED	EACH	63	3			42	12	6	

\* - INDICATES SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

FAP 348 (HARLEM AVENUE)  
BEAUTIFICATION STREETSCAPING  
SUMMARY OF QUANTITIES

SCALE: VERT. NA  
HORIZ. NA  
DATE: 12-19-08

DRAWN BY: PS  
CHECKED BY: RJW

ROBINSON ENGINEERING, LTD.  
17000 SOUTH PARK AVENUE SOUTH HOLLAND, ILLINOIS 60473  
(708) 591-6700 FAX (708) 591-3826  
ILLINOIS DESIGN FIRM REGISTRATION NO. 194001208 07441-QUALIN-01