

SUMMARY OF QUANTITIES					PAVEMENT	MARKINGS	SIGNS	LANDSCAPE	LIGHTS	SIGNALS	TRAINING
S.I.	CODE NO.	PAY ITEM	UNIT	QUAN	CONSTRUCTION TYPE CODE						
					I000	SFTY-1D	Y002-1C	Y003	Y030-1E	Y031	Y080
	40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	1889	1889						
	40600300	AGGREGATE (PRIME COAT)	TON	38	38						
	40600895	CONSTRUCTING TEST STRIP	EACH	2	2						
	40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	820	820						
	40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	1635	1635						
	42300300	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 7 INCH	SQ YD	100	100						
	42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	591	591						
	42400800	DETECTABLE WARNINGS	SQ FT	450	450						
	44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	18074	18074						
	44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	200	200						
	44000600	SIDEWALK REMOVAL	SQ FT	591	591						
	44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	522	522						
	44201753	CLASS D PATCHES, TYPE II, 9 INCH	SQ YD	86	86						
	44201757	CLASS D PATCHES, TYPE III, 9 INCH	SQ YD	292	292						
	44201759	CLASS D PATCHES, TYPE IV, 9 INCH	SQ YD	393	393						
	60250200	CATCH BASINS TO BE ADJUSTED	EACH	5	5						
	60252800	CATCH BASINS TO BE RECONSTRUCTED	EACH	2	2						
	60255500	MANHOLES TO BE ADJUSTED	EACH	10	10						
	60257900	MANHOLES TO BE RECONSTRUCTED	EACH	2	2						
	60266600	VALVE BOXES TO BE ADJUSTED	EACH	2	2						
	60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	2	2						
	67100100	MOBILIZATION	L SUM	1	1						
	70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1						
	70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1						
	70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1						
	70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1						
	70300100	SHORT-TERM PAVEMENT MARKING	FOOT	1000		1000					
*	78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	8688		8688					
*	78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	636		636					
*	78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	704		704					
*	78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	783		783					
	X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	794		794					
	XX006806	HOT-MIX ASPHALT DRIVEWAY PAVEMENT	SQ YD	200	200						

GENERAL NOTES:

- BEFORE STARTING ANY EXCAVATION, THE CONTRACTOR SHALL CALL "J.U.L.I.E." AT (800) 892-0123 AT (312) 744-7000 FOR FIELD LOCATIONS OF BURIED ELECTRIC, TELEPHONE AND GAS UTILITIES. (48 HOUR NOTIFICATION IS REQUIRED).
- UTILITIES INDICATED ON THE PLANS ARE PROVIDED FOR THE CONTRACTORS USE AND ARE BASED UPON INFORMATION AVAILABLE AT THE TIME OF THE ADVERTISEMENT FOR BIDS. THE OWNER AND ENGINEER DO NOT GUARANTEE THE ACCURACY OF UTILITIES INFORMATION.
- IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO VERIFY ALL DIMENSIONS AND CONDITIONS EXISTING IN THE FIELD PRIOR TO CONSTRUCTION AND ORDERING OF MATERIALS.
- SCHEDULES INCLUDED IN THE PLANS HAVE BEEN PREPARED FROM FIELD NOTES. EXACT LOCATIONS FOR PATCHING SHALL BE DETERMINED IN THE FIELD BY THE ENGINEER.
- ANY REFERENCE TO STANDARDS THROUGHOUT THE PLANS OR SPECIAL PROVISIONS SHALL BE INTERPRETED TO BE THE LATEST STANDARDS OF THE ILLINOIS DEPARTMENT OF TRANSPORTATION.
- THE NOMINAL THICKNESS OF HOT-MIX ASPHALT MIXTURE STATED IN THE SPECIFICATIONS IS THE NOMINAL THICKNESS. DEVIATIONS FROM THE NOMINAL THICKNESS WILL BE PERMITTED WHEN SUCH DEVIATIONS OCCUR DUE TO IRREGULARITIES IN THE EXISTING SURFACE OR BASE ON WHICH THE HOT-MIX ASPHALT SURFACE IS PLACED.

* - INDICATES SPECIALTY ITEMS

FILE NAME = 08478-QUAN-01 - 001	USER NAME =	DESIGNED -- RES	REVISED --	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	115TH STREET RESURFACING SUMMARY OF QUANTITIES & GENERAL NOTES WORTH, ILLINOIS			F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		CHECKED -- PKB	REVISED --		1025	08-00056-00-RS	COOK	10	2			
	PLOT SCALE = NONE	DRAWN -- SLG	REVISED --		SCALE: NONE SHEET NO. 2 OF 10 SHEETS STA. -- TO STA. --			FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT M-9003(124)				
	PLOT DATE = 12/18/08	CHECKED -- MJD	REVISED --		CONTRACT NO. 63117							