

SUMMARY OF QUANTITIES					PAVEMENT	MARKINGS
S.I.	CODE NO.	PAY ITEM	UNIT	QUAN	CONSTRUCTION TYPE CODE	
					I000	SFTY-1D
	40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	2700	2700	
	40600895	CONSTRUCTING TEST STRIP	EACH	3	3	
	40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	1050	1050	
	40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	2400	2400	
	42300300	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 7 INCH	SQ YD	160	160	
	42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	7500	7500	
	42400800	DETECTABLE WARNINGS	SQ FT	464	464	
	44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	28700	28700	
	44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	160	160	
	44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	2330	2330	
	44000600	SIDEWALK REMOVAL	SQ FT	7500	7500	
	44201717	CLASS D PATCHES, TYPE II, 6 INCH	SQ YD	60	60	
	44201721	CLASS D PATCHES, TYPE III, 6 INCH	SQ YD	115	115	
	44201723	CLASS D PATCHES, TYPE IV, 6 INCH	SQ YD	1330	1330	
	60200105	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 1 FRAME OPEN LID	EACH	3	3	
	60250200	CATCH BASINS TO BE ADJUSTED	EACH	40	40	
	60255500	MANHOLES TO BE ADJUSTED	EACH	23	23	
	60266600	VALVE BOXES TO BE ADJUSTED	EACH	24	24	
	60500050	REMOVE CATCH BASIN	EACH	3	3	
	60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	2330	2330	
	67100100	MOBILIZATION	L SUM	1	1	
	70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1	
	70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1	
	70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1	
	70300100	SHORT-TERM PAVEMENT MARKING	FOOT	1760		1760
*	78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	150		150
*	78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	9420		9420
*	78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	500		500
*	78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	1330		1330
	X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	1250	1250	
	Z0000940	AGGREGATE FOR DRIVEWAY MAINTENANCE	TON	100	100	
	Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1	
	XX000947	HOT-MIX ASPHALT DRIVEWAY REMOVAL AND REPLACEMENT	SQ YD	150	150	

* - INDICATES SPECIALTY ITEMS

GENERAL NOTES:

- BEFORE STARTING ANY EXCAVATION, THE CONTRACTOR SHALL CALL "J.U.L.I.E." AT (800) 892-0123 AT (312) 744-7000 FOR FIELD LOCATIONS OF BURIED ELECTRIC, TELEPHONE AND GAS UTILITIES. (48 HOUR NOTIFICATION IS REQUIRED).
- UTILITIES INDICATED ON THE PLANS ARE PROVIDED FOR THE CONTRACTORS USE AND ARE BASED UPON INFORMATION AVAILABLE AT THE TIME OF THE ADVERTISEMENT FOR BIDS. THE OWNER AND ENGINEER DO NOT GUARANTEE THE ACCURACY OF UTILITIES INFORMATION.
- IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO VERIFY ALL DIMENSIONS AND CONDITIONS EXISTING IN THE FIELD PRIOR TO CONSTRUCTION AND ORDERING OF MATERIALS.
- SCHEDULES INCLUDED IN THE PLANS HAVE BEEN PREPARED FROM FIELD NOTES. EXACT LOCATIONS FOR PATCHING SHALL BE DETERMINED IN THE FIELD BY THE ENGINEER.
- ANY REFERENCE TO STANDARDS THROUGHOUT THE PLANS OR SPECIAL PROVISIONS SHALL BE INTERPRETED TO BE THE LATEST STANDARDS OF THE ILLINOIS DEPARTMENT OF TRANSPORTATION.
- THE NOMINAL THICKNESS OF HOT-MIX ASPHALT MIXTURE STATED IN THE SPECIFICATIONS IS THE NOMINAL THICKNESS. DEVIATIONS FROM THE NOMINAL THICKNESS WILL BE PERMITTED WHEN SUCH DEVIATIONS OCCUR DUE TO IRREGULARITIES IN THE EXISTING SURFACE OR BASE ON WHICH THE HOT-MIX ASPHALT SURFACE IS PLACED.

FILE NAME = 07485-QUAN-01 - 001	USER NAME =	DESIGNED - RES	REVISED - 02-09-09	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	BROADWAY AVENUE QUANTITIES PARK AVENUE TO SIBLEY BOULEVARD HARVEY, ILLINOIS			F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		CHECKED - SLG	REVISED -			1025	08-00181-00-RS	COOK	10	2		
	PLOT SCALE = N/A	DRAWN - SLG	REVISED -		SCALE: NONE	SHEET NO. 2	OF 10 SHEETS	STA. ---	TO STA. ---	CONTRACT NO. 63117		
	PLOT DATE = 12/18/08	CHECKED - SLG	REVISED -					FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT M-9003(180)		