

SUMMARY OF QUANTITIES

PLAN	SURVEYED	DATE
NOTE BOOK	PLOTTED	BY
NO.	BY	
	DATE	

PROFILE	SURVEYED	DATE
NOTE BOOK	PLOTTED	BY
NO.	BY	
	DATE	

SP	CODED PAY ITEM NUMBER	DESCRIPTION	UNIT OF MEASURE	TOTAL QUANTITY	ROADWAY I000-2A		LIGHTING Y030-1E		UTILITY ADJUSTMENT Y060	
					PARTICIPATING	NON-PARTICIPATING	PARTICIPATING	NON-PARTICIPATING	PARTICIPATING	NON-PARTICIPATING
*	B2000216	TREE, ACER GINNALA (AMUR MAPLE), 2" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	23	23					
*	B2006220	TREE, SYRINGA RETICULATA (JAPANESE TREE LILAC), 2-1/2" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	22	22					
*	B2010016	TREE, AMELANCHIER CANADENSIS (SHADBLow SERVICEBERRY), 2" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	22	22					
* Δ	X0323173	DUCTILE IRON WATER MAIN BEND, 45 DEGREE, 12"	EACH	8						8
* Δ	X0323574	MAINTENANCE OF LIGHTING SYSTEM	CAL MO	6				6		
* Δ	X0323682	BARE COPPER WIRE, NO. 2/0	FOOT	12				12		
*	X0324637	BASE COVER, LIGHT POLE	EACH	16				16		
*	X0351580	PVC WATER MAIN 12"	FOOT	2,672						2,672
* Δ	X0469600	CONNECTION TO EXISTING WATER MAIN	EACH	5						5
Δ	X5510100	STORM SEWER REMOVAL	FOOT	3,597	3,597					
* Δ	X8250400	LIGHTING CONTROLLER PEDESTAL MOUNT	EACH	1				1		
* X007849	X007849	BREAKAWAY DEVICE, COUPLING	EACH	64				64		
*	XX001470	SANITARY SERVICE CONNECTION	EACH	20						20
	XX003668	PRECONSTRUCTION VIDEO TAPING	L SUM	1						
*	XX004907	GATE VALVE, 12" WITH VAULT, 5' DIAMETER	EACH	8						8
*	XX004998	PVC WATER MAIN 6"	FOOT	103						103
*	XX005000	PVC WATER MAIN 10"	FOOT	13						13
* Δ	XX006252	SANITARY SEWER REPLACEMENT WATER MAIN QUALITY	FOOT	600						600
* Δ	XX006937	GROUND ROD, 5/8" DIA. X 10 FT.	EACH	17				17		
Δ	XX007490	HOT-MIX ASPHALT DRIVEWAY PAVEMENT, 8"	SQ YD	881	881					
Δ	Z0001050	AGGREGATE SUBGRADE, 12"	SQ YD	10,679	10,679					
	Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1					
Δ	Z0076600	TRAINEES	HOOR	1,000	1,000					

~ Y080

* INDICATES SPECIALTY ITEM
 Δ INDICATES SPECIAL PROVISION

FILE NAME =	USER NAME = #USER#	DESIGNED - JAB	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
#FILE#		DRAWN - JAB	REVISED -			3003	00-00084-00-PV	DUPAGE	112	8	
PLOT SCALE = #SCALE#		CHECKED - JMT	REVISED -			BLACKHAWK DR RECONSTRUCTION CONTRACT NO. 63121					
PLOT DATE = #DATE#		DATE - 01/02/09	REVISED -			FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT					
					SCALE: NONE	SHEET NO. 5	OF 6 SHEETS	STA.	TO STA.		