| SP REQ'D | SPECIALTY ITEM | CODE NO | DESCRIPTION | UNIT | TOTAL QUANTITY | I000 | Y003 | Y007 | NON-PARTICIPATING |
|---|---|---|---|---|---|---|---|---|---|
| | * | 20101350 | TREE PRUNING (OVER 10 INCH DIAMETER) | EACH | 6 | --- | 6 | --- | --- |
| | | 20200100 | EARTH EXCAVATION | CU YD | 180 | 180 | --- | --- | --- |
| | | 20201200 | REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL | CU YD | 1340 | 1340 | --- | --- | --- |
| Y | | 20700420 | POROUS GRANULAR EMBANKMENT, SUBGRADE | CU YD | 1135 | 1135 | --- | --- | --- |
| Y | | 20800250 | TRENCH BACKFILL, SPECIAL | CU YD | 210 | --- | --- | 210 | --- |
| | | 21001000 | GEOTECHNICAL FABRIC FOR GROUND STABILIZATION | SQ YD | 6200 | 6200 | --- | --- | --- |
| | | 21101505 | TOPSOIL EXCAVATION AND PLACEMENT | CU YD | 114 | --- | 114 | --- | --- |
| | * | 25000400 | NITROGEN FERTILIZER NUTRIENT | POUND | 10 | --- | 10 | --- | --- |
| | * | 25000500 | PHOSPHORUS FERTILIZER NUTRIENT | POUND | 10 | --- | 10 | --- | --- |
| | * | 25000600 | POTASSIUM FERTILIZER NUTRIENT | POUND | 10 | --- | 10 | --- | --- |
| | * | 25200200 | SUPPLEMENTAL WATERING | UNIT | 15 | --- | 15 | --- | --- |
| | * | 25200110 | SODDING, SALT TOLERANT | SQ YD | 420 | --- | 420 | --- | --- |
| | | 28000510 | INLET FILTERS | EACH | 36 | 36 | --- | --- | --- |
| Y | | 35800100 | PREPARATION OF BASE | SQ YD | 11715 | 11715 | --- | --- | --- |
| Y | | 35800200 | AGGREGATE BASE REPAIR | TON | 750 | 750 | --- | --- | --- |
| | | 40600100 | BITUMINOUS MATERIALS (PRIME COAT) | GAL | 5275 | 5275 | --- | --- | --- |
| | | 40600300 | AGGREGATE (PRIME COAT) | TON | 36 | 36 | --- | --- | --- |
| | | 40600895 | CONSTRUCTING TEST STRIP | EACH | 2 | 2 | --- | --- | --- |
| | | 40603080 | HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50 | TON | 2625 | 2625 | --- | --- | --- |
| | | 40603335 | HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50 | TON | 1313 | 1313 | --- | --- | --- |
| | | 42300300 | PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 7 INCH | SQ YD | 12 | 12 | --- | --- | --- |
| Y | | 42400430 | PORTLAND CEMENT CONCRETE SIDEWALK, 5 INCH, SPECIAL | SQ FT | 11660 | 11660 | --- | --- | --- |
| | | 42400800 | DETECTABLE WARNINGS | SQ FT | 540 | 540 | --- | --- | --- |
| | | 44000200 | DRIVEWAY PAVEMENT REMOVAL | SQ YD | 23 | 23 | --- | --- | --- |
| | | 44000500 | COMBINATION CURB & GUTTER REMOVAL | FOOT | 1529 | 1529 | --- | --- | --- |
| | | 44000600 | SIDEWALK REMOVAL | SQ FT | 6200 | 6200 | --- | --- | --- |
| Y | | 44004400 | PAVEMENT REMOVAL (SPECIAL) | SQ YD | 11644 | 11644 | --- | --- | --- |
| | | 550A0040 | STORM SEWERS, CLASS A, TYPE 1 10" | FOOT | 19 | --- | --- | 19 | --- |
| | | 550A0050 | STORM SEWERS, CLASS A, TYPE 1 12" | FOOT | 82 | --- | --- | 82 | --- |
| | | 550A0340 | STORM SEWERS, CLASS A, TYPE 2 12" | FOOT | 125 | --- | --- | 125 | --- |
| | | 550A0380 | STORM SEWERS, CLASS A, TYPE 2 18" | FOOT | 5 | --- | --- | 5 | --- |
| | | 550A0710 | STORM SEWERS, CLASS A, TYPE 3 24" | FOOT | 10 | --- | --- | 10 | --- |
| | | 55100300 | STORM SEWER REMOVAL 8" | FOOT | 39 | --- | --- | 39 | --- |
| | | 55100400 | STORM SEWER REMOVAL 10" | FOOT | 101 | --- | --- | 101 | --- |
| | | 55100500 | STORM SEWER REMOVAL 12" | FOOT | 37 | --- | --- | 37 | --- |
| | | 55100900 | STORM SEWER REMOVAL 18" | FOOT | 10 | --- | --- | 10 | --- |
| | | 55101200 | STORM SEWER REMOVAL 24" | FOOT | 20 | --- | --- | 20 | --- |
| Y | * | 56103000 | DUCTILE IRON WATER MAIN 6" | FOOT | 81 | --- | --- | 81 | --- |
| Y | * | 56201400 | CORPORATION STOPS 1" | EACH | 1 | --- | --- | 1 | --- |
| Y | * | 56400800 | FIRE HYDRANT AND VALVE TO BE MOVED | EACH | 3 | --- | --- | 3 | --- |
| Y | * | 56500700 | DOMESTIC WATER SERVICE BOXES TO BE REMOVED | EACH | 1 | --- | --- | 1 | --- |
| Y | * | 56500800 | DOMESTIC WATER SERVICE BOXES | EACH | 1 | --- | --- | 1 | --- |
| | | 60200105 | CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, OPEN LID | EACH | 27 | --- | --- | 27 | --- |
| | | 60218300 | MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, OPEN LID | EACH | 1 | --- | --- | 1 | --- |
| | | 60218400 | MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID | EACH | 3 | --- | --- | 3 | --- |
| Y | | 60406100 | FRAMES AND LIDS, TYPE 1, CLOSED LID | EACH | 15 | --- | --- | 15 | --- |
| | | 60600605 | CONCRETE CURB, TYPE B | FOOT | 1003 | --- | 1003 | --- | --- |
| Y | | 60604200 | COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12 (SPECIAL) | FOOT | 1825 | 1825 | --- | --- | --- |
| | | 66900205 | SPECIAL WASTE DISPOSAL | CU YD | 8 | 8 | --- | --- | --- |
| | | 67100100 | MOBILIZATION | L SUM | 1 | 1 | --- | --- | --- |
| Y | | 70101800 | TRAFFIC CONTROL AND PROTECTION (SPECIAL) | L SUM | 1 | 1 | --- | --- | --- |
| | | 72800100 | TELESCOPING STEEL SIGN SUPPORT | FOOT | 70 | 70 | --- | --- | --- |
| | | 73100100 | BASE FOR TELESCOPING STEEL SIGN SUPPORT | EACH | 10 | 10 | --- | --- | --- |
| | * | 78000100 | THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS | SQ FT | 146 | 146 | --- | --- | --- |
| | * | 78000200 | THERMOPLASTIC PAVEMENT MARKING - LINE 4" | FOOT | 7740 | 7740 | --- | --- | --- |
| | * | 78000400 | THERMOPLASTIC PAVEMENT MARKING - LINE 6" | FOOT | 2070 | 2070 | --- | --- | --- |
| | * | 78000600 | THERMOPLASTIC PAVEMENT MARKING - LINE 12" | FOOT | 225 | 225 | --- | --- | --- |
| | * | 78000650 | THERMOPLASTIC PAVEMENT MARKING - LINE 24" | FOOT | 266 | 266 | --- | --- | --- |
| | * | 81000600 | CONDUIT IN TRENCH, 2" DIA., GALVINIZED STEEL | FOOT | 465 | 465 | --- | --- | --- |
| | * | 81017515 | CONDUIT IN TRENCH, 1 1/4" DIA., COILABLE NONMETALLIC CONDUIT | FOOT | 95 | 95 | --- | --- | --- |
| Y | * | 81030100 | CONDUIT SPLICE | EACH | 7 | 7 | --- | --- | --- |
| | * | 81702415 | ELECTRIC CABLE IN CONDUIT, 600V, (XLP-TYPE USE) 3-1/C NO. 6 | FOOT | 550 | 550 | --- | --- | --- |
| | * | 81900200 | TRENCH AND BACKFILL FOR ELECTRICAL WORK | FOOT | 900 | 900 | --- | --- | --- |
| | * | 83600200 | LIGHT POLE FOUNDATION, 24" DIAMETER | FOOT | 94 | 94 | --- | --- | --- |
| Y | * | 83600215 | LIGHT POLE FOUNDATION, 24" DIAMETER, OFFSET | FOOT | 70 | 70 | --- | --- | --- |
| | * | 84200700 | LIGHTING FOUNDATION REMOVAL | EACH | 5 | 5 | --- | --- | --- |
| | * | 84400105 | RELOCATE EXISTING LIGHTING UNIT | EACH | 5 | 5 | --- | --- | --- |
| | * | 87900100 | DRILL EXISTING FOUNDATION | EACH | 2 | 2 | --- | --- | --- |
| Y | | 88600600 | DETECTOR LOOP REPLACEMENT | FOOT | 225 | 225 | --- | --- | --- |
| Y | * | K0030409 | PERENNIAL, CAMPANULA CARPATICA 'BLUE CLIPS', (BLUE CLIPS CARPATHIAN HAREBELL), 1-QUART | EACH | 183 | --- | 183 | --- | --- |
| Y | * | K0039125 | HEMEROCALLIS 'HAPPY RETURNS' CONTAINER GROWN, 1-GALLON | UNIT | 1,7 | --- | 1,7 | --- | --- |
| Y | * | K1005481 | SHREDDED BARK MULCH 3" | SQ YD | 202 | --- | 202 | --- | --- |
| Y | * | X0321478 | MAINTENANCE OF EXISTING LIGHTING SYSTEMS | L SUM | 1 | 1 | --- | --- | --- |
| Y | * | X0322951 | CABLE SPLICE, SPECIAL | EACH | 7 | 7 | --- | --- | --- |
| Y | | X0712400 | TEMPORARY PAVEMENT | SQ YD | 260 | --- | --- | 260 | --- |
| Y | | X4021000 | TEMPORARY ACCESS (PRIVATE ENTRANCE) | EACH | 32 | 32 | --- | --- | --- |
| Y | | X4022000 | TEMPORARY ACCESS (COMMERCIAL ENTRANCE) | EACH | 2 | 2 | --- | --- | --- |
| Y | | X4023000 | TEMPORARY ACCESS (ROAD) | EACH | 15 | 15 | --- | --- | --- |
| Y | * | X8950215 | RELOCATE EXISTING HANDHOLE | EACH | 2 | 2 | --- | --- | --- |
| Y | | XX002260 | STRUCTURES TO BE REMOVED | EACH | 11 | --- | --- | 11 | --- |
| Y | * | XX004887 | ORNAMENTAL LIGHT UNIT, COMPLETE | EACH | 16 | 16 | --- | --- | --- |
| Y | | XX005450 | STORM SEWER WATER MAIN QUALITY 12" | FOOT | 193 | --- | --- | 193 | --- |
| Y | | XX005541 | CURED-IN-PLACE PIPE (CIPP), 12" | FOOT | 140 | --- | --- | --- | 140 |
| Y | | XX005554 | CURED-IN-PLACE PIPE (CIPP), 24" | FOOT | 190 | --- | --- | --- | 190 |
| Y | | XX006591 | PAVEMENT TEXTURING | SQ FT | 4950 | 4950 | --- | --- | --- |
| Y | * | XX006937 | GROUND ROD, 5/8" DIA. X 10FT. | EACH | 21 | 21 | --- | --- | --- |
| Y | | XX006952 | CATCH BASINS, 4' DIAMETER, TYPE 1 FRAME, OPEN LID, WITH HALF TRAP | EACH | 2 | --- | --- | 2 | --- |
| Y | * | XX011700 | WATER MAIN FITTINGS | POUND | 385 | --- | --- | 385 | --- |
| Y | | Z0001050 | AGGREGATE SUBGRADE 12" | SQ YD | 200 | 200 | --- | --- | --- |
| Y | | Z0013798 | CONSTRUCTION LAYOUT | L SUM | 1 | 1 | --- | --- | --- |
| Y | | Z0017400 | DRAINAGE & UTILITY STRUCTURES TO BE ADJUSTED | EACH | 60 | --- | --- | 60 | --- |
| Y | | Z0017700 | DRAINAGE & UTILITY STRUCTURES TO BE RECONSTRUCTED | EACH | 5 | --- | --- | 5 | --- |
| Y | | Z0019600 | DUST CONTROL WATERING | UNIT | 150 | 150 | --- | --- | --- |
| Y | △ | Z0076600 | TRAINEES | HOUR | 500 | 500 | --- | --- | --- |
| Y | * | XX007668 | COPPER SERVICE, TYPE K 2" (BORED) | FOOT | 50 | --- | --- | 50 | --- |
| Y | * | XX007668 | COPPER SERVICE, TYPE K 2" (TRENCHED) | FOOT | 50 | --- | --- | 50 | --- |
| Y | * | XX007850 | HEMEROCALLIS 'LITTLE WINE CUP' (LITTLE WINE CUP DAYLILY), 1-GALLON CONTAINER | EACH | 97 | --- | 97 | --- | --- |
| Y | | XX007851 | PEDESTRIAN BENCH, FURNISH | EACH | 1 | 1 | --- | --- | --- |
| Y | | XX007852 | PEDESTRIAN BENCH, FURNISH AND INSTALL | EACH | 11 | 11 | --- | --- | --- |
| Y | | XX007853 | PVC STORM AND SAN SEWER R&R 12" DIA, 0-15 FT LENGTH | EACH | 1 | --- | --- | --- | 1 |
| Y | | XX007854 | PVC STORM AND SAN SEWER R&R 12" DIA, 16-30 FT LENGTH | EACH | 1 | --- | --- | --- | 1 |
| Y | * | K0030428 | PERENNIAL PLANTS, STOKESIA LAEVIS 'HETERO LEPIS' (PRAIRIE DISPLEASE) 1-GALLON CONTAINER | EACH | 50 | --- | 50 | --- | --- |
| Y | | XX007855 | STORM SEWER WATER MAIN QUALITY 10" | FOOT | 136 | --- | --- | 136 | --- |
| Y | | XX007856 | TRASH RECEPTACLE, FURNISH | EACH | 1 | 1 | --- | --- | --- |
| Y | | XX007857 | TRASH RECEPTACLE, FURNISH AND INSTALL | EACH | 11 | 11 | --- | --- | --- |
| Y | * | XX007858 | TREE, ACER X FREEMANII AUTUMN BLAZE (AUTUMN BLAZE FREEMAN MAPLE), 4" CALIPER, BALLED AND BURLAPPED | EACH | 11 | --- | 11 | --- | --- |
| Y | * | XX007859 | UNIT DUCT, 600V. 1/C #6, 1/C #6 NEUTRAL & 1/C #6 GND. (XLP TYPE-USE) IN 1 1/4 " DIA. SCH 40 HDPE, IN TRENCH | FOOT | 920 | 920 | --- | --- | --- |

△ Y080

| FILE NAME = | USER NAME = PRAZALAN | DESIGNED - | REVISED - |
|---|---|---|---|
| N:\FORESTPARK\070081\C1v1\QUA_070081_01.SHT | | DRAWN - | REVISED - |
| | PLOT SCALE = N.T.S. | CHECKED - | REVISED - |
| | PLOT DATE = 2/17/2009 | DATE - | REVISED - |

**STATE OF ILLINOIS**
**DEPARTMENT OF TRANSPORTATION**

**SUMMARY OF QUANTITIES – JACKSON BOULEVARD**

SCALE: | SHEET NO. OF SHEETS | STA. | TO STA.

| F.A. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
|---|---|---|---|---|
| 1462 | 07-00105-00-PV | COOK | 49 | 6 |
| | | CONTRACT NO. 63134 | | |
| FED. ROAD DIST. NO. 1 | ILLINOIS | FED. AID PROJECT | | |