

SUMMARY OF QUANTITIES

ITEM NO.	ITEMS	UNIT	1000-2A QUANTITY
35101800	AGGREGATE BASE COURSE, TYPE B 6"	SQ YD	360
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	20
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GAL	2214
40600300	AGGREGATE (PRIME COAT)	TON	45
40600895	CONSTRUCTING TEST STRIP	EACH	2
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX C, N50, 3"	TON	62
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX D, N70, 1 1/2"	TON	3647
42000300	PORTLAND CEMENT CONCRETE PAVEMENT, 8"	SQ YD	70
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	500
42400800	DETECTABLE WARNINGS	EACH	11
44000151	HOT MIX ASPHALT SURFACE REMOVAL, 1/2"	SY	28425
44000157	HOT MIX ASPHALT SURFACE REMOVAL, 2"	SY	5707
44000100	PAVEMENT REMOVAL, 10"	SQ YD	70
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	360
44000600	SIDEWALK REMOVAL	SQ FT	500
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	LF	150
44201713	CLASS D PATCHES, TYPE I, 6 INCH	SQ YD	465
44201717	CLASS D PATCHES, TYPE II, 6 INCH	SQ YD	465
44201721	CLASS D PATCHES, TYPE III, 6 INCH	SQ YD	465
44201723	CLASS D PATCHES, TYPE IV, 6 INCH	SQ YD	465
44300100	AREA REFLECTIVE CRACK CONTROL TREATMENT	SY	5707
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	LF	36440
48101200	AGGREGATE SHOULDER, TYPE B	TON	434
67100100	MOBILIZATION	L. SUM	1
70101700	TRAFFIC CONTROL AND PROTECTION	L. SUM	1
70300220	TEMPORARY PAVEMENT MARKING LINE - 4"	FOOT	9110
*78000100	THERMOPLASTIC PAVEMENT MARKINGS - LETTERS AND SYMBOLS	SF	722
*78000200	THERMOPLASTIC PAVEMENT MARKINGS - LINE 4"	LF	30250
*78000400	THERMOPLASTIC PAVEMENT MARKINGS - LINE 6"	LF	4600
*78000600	THERMOPLASTIC PAVEMENT MARKINGS - LINE 12"	LF	425
*78000650	THERMOPLASTIC PAVEMENT MARKINGS - LINE 24"	LF	575
*78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	190
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	185
*88600600	DETECTOR LOOP REPLACEMENT	LF	1032
XX002258	STRUCTURE ADJUSTMENT	EACH	5
Z0013798	CONSTRUCTION LAYOUT	L. SUM	1
X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50, 3/4"	TON	1823
44000190	HOT MIX ASPHALT SURFACE REMOVAL, SPECIAL	SY	8148

*INDICATES SPECIALTY ITEM

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: NTS SHEET NO. OF SHEETS STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
0035	08-00033-00-RS	MCHEMRY	19	2
CONTRACT NO. 63141			ILLINOIS FED. AID PROJECT	

FILE NAME = USER NAME = MAGOLDEN
 N:\Huntley\070103\070103.0001\Civil\ques.70103.0001.dwt
 PLOT SCALE = NTS
 PLOT DATE = 2/25/2009

DESIGNED - LMF
 DRAWN - MAG
 CHECKED - LMF
 DATE - 2/25/2009

REVISED -
 REVISED -
 REVISED -
 REVISED -