

**SUMMARY OF QUANTITIES**

CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY	ROADWAY I000	
				HALIGUS ROAD	HUNTLEY ROAD
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	2,345	920	1,425
40600300	AGGREGATE (PRIME COAT)	TON	48	19	29
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	340	212	128
40600895	CONSTRUCTING TEST STRIP	EACH	3	1	2
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	735	155	580
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	127	102	25
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	290	290	-
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	580	-	580
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SQ YD	6,825	970	5,855
44002210	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 2 1/2"	SQ YD	876	706	170
44201705	CLASS D PATCHES, TYPE II, 5 INCH	SQ YD	195	70	125
44201709	CLASS D PATCHES, TYPE III, 5 INCH	SQ YD	290	105	185
44201711	CLASS D PATCHES, TYPE IV, 5 INCH	SQ YD	1,430	520	910
44201729	CLASS D PATCHES, TYPE II, 7 INCH	SQ YD	25	-	25
44201733	CLASS D PATCHES, TYPE III, 7 INCH	SQ YD	35	-	35
44201735	CLASS D PATCHES, TYPE IV, 7 INCH	SQ YD	165	-	165
44300100	AREA REFLECTIVE CRACK CONTROL TREATMENT	SQ YD	11,725	4,600	7,125
48101200	AGGREGATE SHOULDERS, TYPE B	TON	460	190	270
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	9	-	9
67100100	MOBILIZATION	LSUM	1	0.40	0.60
70101700	TRAFFIC CONTROL AND PROTECTION	LSUM	1	0.40	0.60
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	7,424	3,008	4,416
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	619	251	368
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	18,500	7,500	11,000
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	60	-	60
X0321556	SANITARY MANHOLES TO BE ADJUSTED	EACH	1	-	1
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	182	52	130

\* INDICATES SPECIALTY ITEM

**SCHEDULE OF QUANTITIES**

**HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT**

LOCATION	AREA (SQ YD)
HALIGUS ROAD, SOUTH LIMITS (STA 8+15)	15
HALIGUS ROAD, NORTH LIMITS (STA 26+45)	15
HALIGUS ROAD, HMA AND GRAVEL DRIVEWAYS	125
HUNTLEY ROAD, SOUTH LIMITS (STA 110+70)	15
HUNTLEY ROAD, AT SHADE TREE CIRCLE (STA 128+60)	30
HUNTLEY ROAD, AT OAKWOOD DRIVE (STA 110+38, LT)	20
HUNTLEY ROAD, AT OAKWOOD DRIVE (STA 110+38, RT)	25
HUNTLEY ROAD, NORTH LIMITS (STA 137+70)	45
HUNTLEY ROAD, HMA AND GRAVEL DRIVEWAYS	445
<b>TOTAL</b>	<b>735</b>

COPYRIGHT © 2008 BY BAXTER & WOODMAN, INC.  
 STATE OF ILLINOIS - PROFESSIONAL DESIGN FIRM  
 LICENSE NO. - BR-002171 - EXPIRES 4/30/2009  
 7/28/2009  
 6045447.DWG  
 \\p10175.0808057-pentagon\h10175...  
 \\p10175.0808057-pentagon\h10175...  
 \\p10175.0808057-pentagon\h10175...  
 \\p10175.0808057-pentagon\h10175...



DESIGNED - REW	REVISED - 1-20-09 - IDOT REVIEW
DRAWN - UKB	REVISED -
CHECKED - RWL	REVISED -
DATE - 12-08-08	REVISED -

**VILLAGE OF LAKEWOOD, ILLINOIS  
HALIGUS ROAD AND HUNTLEY ROAD STP (LAPP)  
IMPROVEMENTS**

**SUMMARY OF QUANTITIES  
AND SCHEDULE OF QUANTITIES**

SCALE: NONE

STA: TO STA:

*F.A.U. 3869 HALIGUS ROAD AND F.A.U. 0118 HUNTLEY ROAD				
F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	08-00010-00-RS	MCHEMRY	17	3
FED. ROAD DIST. NO. 1			CONTRACT NO. 63145	
C-91-207-09			ILLINOIS FED. AID PROJECT M-9003 (175)	