

SP REQ'D	SPECIALTY ITEM	CODE NO	DESCRIPTION	UNIT	TOTAL QUANTITY	1000-2A		Y003		Y007		VILLAGE QUANTITY
						HPP QUANTITY	STP QUANTITY	HPP QUANTITY	STP QUANTITY	HPP QUANTITY	STP QUANTITY	
	*	84200700	LIGHTING FOUNDATION REMOVAL	EACH	5		5					
	*	84400105	RELOCATE EXISTING LIGHTING UNIT	EACH	3		3					
	*	C2007224	SHRUB, ROSA KNOCKOUT (KNOCKOUT ROSE), 24" HEIGHT, CONTAINER	EACH	28				28			
Y	*	K0030409	PERENNIAL, CAMPANULA CARPATICA 'BLUE CLIPS', (BLUE CLIPS CARPATHIAN HAREBELL), 1-QUART	EACH	208				208			
Y	*	K0039125	HEMEROCALLIS 'HAPPY RETURNS' CONTAINER GROWN, 1-GALLON	UNIT	182				182			
Y	*	K1005481	SHREDDED BARK MULCH 3"	SQ YD	570				570			
Y	*	X0301335	WATER MAIN REMOVAL 8"	FOOT	25							25
Y	*	X0301430	PRECAST CONCRETE PARKING BLOCK	EACH	7		7					
Y	*	X0321478	MAINTENANCE OF EXISTING LIGHTING SYSTEMS	L SUM	1		1					
Y	*	X0322951	CABLE SPLICE, SPECIAL	EACH	9		9					
Y	*	X0323449	REMOVE EXISTING WATER VALVE	EACH	4							4
Y	*	X0323455	ADJUST MONITORING WELLS	EACH	4		4					
Y	*	X0323814	SANITARY SEWER REMOVAL, 18"	FOOT	10		10					
Y	*	X0323988	TEMPORARY SOIL RETENTION SYSTEM	SQ FT	500							500
Y	*	X0712400	TEMPORARY PAVEMENT	SQ YD	150		150					
Y	*	X4021000	TEMPORARY ACCESS (PRIVATE ENTRANCE)	EACH	50	50						
Y	*	X4022000	TEMPORARY ACCESS (COMMERCIAL ENTRANCE)	EACH	3	3						
Y	*	X4023000	TEMPORARY ACCESS (ROAD)	EACH	20	20						
Y	*	X8950130	MODIFY EXISTING LIGHTING CONTROLLER	EACH	4		4					
Y	*	X8950215	RELOCATE EXISTING HANDHOLE	EACH	3		3					
Y	*	XX000479	WATER MAIN REMOVAL 6 INCH	FOOT	345							345
Y	*	XX001011	BICYCLE RACKS	EACH	1		1					
Y	*	XX001446	PLUG AND BLOCK WATER MAIN	EACH	54							54
Y	*	XX002082	SANITARY SEWER REMOVAL 24"	FOOT	324		10					314
Y	*	XX002260	STRUCTURES TO BE REMOVED	EACH	26						16	10
Y	*	XX003352	SANITARY SEWER REMOVAL 27"	FOOT	10		10					
Y	*	XX004887	ORNAMENTAL LIGHT UNIT, COMPLETE	EACH	16		16					
Y	*	XX005195	COMBINED SEWER MANHOLE, 4'-DIAMETER TYPE 1 FRAME, CLOSED LID	EACH	1						1	
Y	*	XX005308	HEMEROCALLIS 'STELLA D'ORO' CONTAINER GROWN (1 GALLON)	EACH	440				440			
Y	*	XX005450	STORM SEWER WATER MAIN QUALITY 12"	FOOT	313						313	
Y	*	XX005544	CURED-IN-PLACE PIPE (CIPP), 18"	FOOT	283							283
Y	*	XX005695	SANITARY SEWER SERVICE LEADS RELOCATE AND RECONNECT	FOOT	30							30
Y	*	XX005701	ALLEY APRON APPROACH PAVEMENT REMOVAL	SQ YD	93		93					
Y	*	XX006259	STEEL CASING PIPE 20"	FOOT	132							132
Y	*	XX006591	PAVEMENT TEXTURING	SQ FT	7860		7860					
Y	*	XX006937	GROUND ROD, 5/8" DIA. X 10FT.	EACH	21		21					
Y	*	XX006952	CATCH BASINS, 4' DIAMETER, TYPE 1 FRAME, OPEN LID, WITH HALF TRAP	EACH	24						24	
Y	*	XX011700	WATER MAIN FITTINGS	POUND	4100							4100
Y	*	Z0001050	AGGREGATE SUBGRADE 12"	SQ YD	18230	18230						
Y	*	Z0007601	BUILDING REMOVAL NO. 1	L SUM	1	1						

SP REQ'D	SPECIALTY ITEM	CODE NO	DESCRIPTION	UNIT	TOTAL QUANTITY	1000-2A		Y003		Y007		VILLAGE QUANTITY
						HPP QUANTITY	STP QUANTITY	HPP QUANTITY	STP QUANTITY	HPP QUANTITY	STP QUANTITY	
Y	*	Z0007602	BUILDING REMOVAL NO. 2	L SUM	1	1						
Y	*	Z0013798	CONSTRUCTION LAYOUT	L SUM	1		1					
Y	*	Z0017400	DRAINAGE & UTILITY STRUCTURES TO BE ADJUSTED	EACH	90						90	
Y	*	Z0017700	DRAINAGE & UTILITY STRUCTURES TO BE RECONSTRUCTED	EACH	5						5	
Y	*	Z0019600	DUST CONTROL WATERING	UNIT	150		150					
Y	*	Z0049801	REMOVAL AND DISPOSAL OF FRIABLE ASBESTOS, BUILDING NO. 1	L SUM	1		1					
Y	*	Z0049802	REMOVAL AND DISPOSAL OF FRIABLE ASBESTOS, BUILDING NO. 2	L SUM	1		1					
Y	*	Z0049901	REMOVAL AND DISPOSAL OF NON-FRIABLE ASBESTOS, BUILDING NO. 1	L SUM	1		1					
Y	*	Z0049902	REMOVAL AND DISPOSAL OF NON-FRIABLE ASBESTOS, BUILDING NO. 2	L SUM	1		1					
Y	*	Z0057300	SANITARY SEWER 18"	FOOT	5		5					
Y	*	Z0057500	SANITARY SEWER 24"	FOOT	319		5					314
Y	*	Z0057600	SANITARY SEWER 27"	FOOT	5		5					
Y	*	Z0057700	SANITARY SEWER 30"	FOOT	5		5					
Y	*	Z0076600	TRAINEES	HOUR	1000		1000					
Y	*	Z0077900	WOOD POST AND RAIL FENCE	FOOT	120		120					
Y	*	XX007669	COPPER SERVICE, TYPE K 1" (BORED)	FOOT	50							50
Y	*	XX007668	COPPER SERVICE, TYPE K 1" (TRENCHED)	FOOT	40							40
Y	*	XX007893	ASBESTOS SURVEY AND REPORT	EACH	2		2					
Y	*	XX007894	ALLEY APRON APPROACH PAVEMENT REMOVAL	SQ YD	340		340					
Y	*	XX007895	COMBINED SEWER MANHOLE, 5'-DIAMETER TYPE 1 FRAME, CLOSED LID	EACH	4						4	
Y	*	XX007896	CURED-IN-PLACE PIPE (CIPP), 30"	FOOT	162							162
Y	*	XX007897	GERANIUM PRATENSE 'MIDNIGHT REITER' (MIDNIGHT REITER GERANIUM), 1-GALLON CONTAINER	EACH	72				72			
Y	*	XX007898	HEMEROCALLIS 'LITTLE WINE CUP' (LITTLE WINE CUP DAYLILY), 1-GALLON CONTAINER	EACH	163				163			
Y	*	XX007898	HEMEROCALLIS 'ROSY RETURNS' (ROSY RETURNS DAYLILY), 1-GALLON CONTAINER	EACH	196				196			
Y	*	XX007899	MASONRY WALL	FOOT	137		137					
Y	*	XX007901	PEDESTRIAN BENCH, FURNISH	EACH	2		2					
Y	*	XX007902	PEDESTRIAN BENCH, FURNISH AND INSTALL	EACH	14		14					
Y	*	XX007900	PVC STORM AND SAN SEWER R&R 15" DIA, 41-50 FT LENGTH	EACH	1							1
Y	*	XX007901	RELOCATE EXISTING LIGHTING UNIT, SPECIAL	EACH	2		2					
Y	*	XX007901	SANITARY SEWER REMOVAL 30"	FOOT	10		10					
Y	*	XX007902	PERENNIAL BITIS SPOROBIOLUS (PRAIRIE DROPSEED), 1-GALLON CONTAINER	EACH	72				72			
Y	*	XX007903	STORM SEWER WATER MAIN QUALITY 10"	FOOT	137						137	
Y	*	XX007904	TRASH RECEPTACLE, FURNISH	EACH	1		1					
Y	*	XX007905	TRASH RECEPTACLE, FURNISH AND INSTALL	EACH	15		15					
Y	*	XX007906	TREE ULMUS ACCOLADE (HYBRID ELM) 4" CALIPER, BALLED AND BURLAPPED	EACH	11				11			
Y	*	XX007907	TREE ACER X FREEMANI AUTUMN BLAZE (AUTUMN BLAZE FREEMAN MAPLE) 4" CALIPER, BALLED AND BURLAPPED	EACH	14				14			
Y	*	XX007908	UNIT DUCT, 600V, 1/C #10, 1/C #10 NEUTRAL & 1/C #10 GND. (XLP TYPE-USE) IN 1" DIA. SCH 40 HDPE, BORED & PULLED	FOOT	1970		1970					
Y	*	XX007909	UNIT DUCT, 600V, 2/C #6, 2/C #6 NEUTRAL & 1/C #6 GND. (XLP TYPE-USE) IN 1 1/4" DIA. SCH 40 HDPE, BORED & PULLED	FOOT	200		200					

Δ Y080