

SUMMARY OF QUANTITIES

ACRS Y007	ACBRS X028-2A
Ogle County 80% FED / 20% STATE	

CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY	SN# 071-1147	SN# 071-2027
20100500	TREE REMOVAL, ACRES	ACRE	0.50	0.50	
20101000	TEMPORARY FENCE	FOOT	232	232	
20200100	EARTH EXCAVATION	CU YD	1980	346	1634
20200200	ROCK EXCAVATION	CU YD	33	33	
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	225		225
20300100	CHANNEL EXCAVATION	CU YD	50		50
20400800	FURNISHED EXCAVATION	CU YD	120	120	
21301052	EXPLORATION TRENCH 52" DEPTH	FOOT	840	20	820
* 25000100	SEEDING, CLASS 1	ACRE	0.25	0.25	
* 25000210	SEEDING, CLASS 2A	ACRE	1.00	0.30	0.70
* 25000310	SEEDING, CLASS 4	ACRE	0.50	0.20	0.30
+ * 25000750	MOWING	ACRE	1.20	0.50	0.70
* 25100115	MULCH, METHOD 2	ACRE	1.20	0.50	0.70
* 25100630	EROSION CONTROL BLANKET	SQ YD	4022.0	661	3361
* 25100900	TURF REINFORCEMENT MAT	SQ YD	96.0	96	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	496	96	400
28000300	TEMPORARY DITCH CHECKS	EACH	30	18	12
28000400	PERIMETER EROSION BARRIER	FOOT	259	259	
28000500	INLET AND PIPE PROTECTION	EACH	3	2	1
28100107	STONE RIPRAP, CLASS A4	SQ YD	106	44	62
28200200	FILTER FABRIC	SQ YD	106	44	62
35101400	AGGREGATE BASE COURSE, TYPE B	TON	168	68	100
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	151	80	71
40600895	CONSTRUCTING TEST STRIP	EACH	2	1	1
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	300	150	150
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	258	135	123
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	27	27	
44201383	CLASS C PATCHES, TYPE IV, 12 INCH	SQ YD	226		226
44201396	CLASS C PATCHES, TYPE IV, 13 INCH	SQ YD	210	210	
48101200	AGGREGATE SHOULDERS, TYPE B	TON	540	277	263
48203019	HOT-MIX ASPHALT SHOULDERS, 5 1/2"	SQ YD	294	156	138
50100300	REMOVAL OF EXISTING STRUCTURES, NO. 1	EACH	1		1

* SPECIALTY ITEMS † NON-PARTICIPATING 100% STATE

FILE NAME = c:\pwork\pwork\cushmanbw\dms37281\0271185-ahh-500.dgn	USER NAME = cushmanbw	DESIGNED - DRAWN -	REVISED - REVISED - REVISED - REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.S RTE. 1042	SECTION 107T-1	COUNTY OGLE	TOTAL SHEETS 53	SHEET NO. 2
PLOT SCALE = 50,0000' / IN. PLOT DATE = Mon Dec 01 13:06:00 2008		CHECKED - DATE -	REVISED -	SCALE: SHEET NO. OF SHEETS STA. TO STA.		FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT CONTRACT NO. 64B09				