

SUMMARY OF QUANTITIES

CODE NUMBER	ITEM	UNIT	90% FED. 10% STATE 1000-1A TOTAL
60221100	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1
60608600	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-8.06	FOOT	51
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT	157
63500105	DELINEATORS	EACH	6
66700305	PERMANENT SURVEY MARKERS, TYPE II	EACH	1
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6
67100100	MOBILIZATION	L SUM	1
70100200	TRAFFIC CONTROL AND PROTECTION, STANDARD 701331	EACH	1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	20
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	1584
70300610	TEMPORARY PAINT PAVEMENT MARKING, LETTERS AND SYMBOLS	SQ FT	31.2
70300625	TEMPORARY PAINT PAVEMENT MARKING LINE 4"	FOOT	35000
70300660	TEMPORARY PAINT PAVEMENT MARKING LINE 24"	FOOT	36
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	6928
70400100	TEMPORARY CONCRETE BARRIER	FOOT	150
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	124.8
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	14929
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	726
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	713
* SPECIALTY ITEMS			
X SEE SPECIAL PROVISIONS			

CODE NUMBER	ITEM	UNIT	90% FED. 10% STATE 1000-1A TOTAL
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	30
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	144
78300100	PAVEMENT MARKING REMOVAL	SQ FT	4200
* 80400100	ELECTRIC SERVICE INSTALLATION	EACH	1
* 81020500	CONDUIT PUSHED, 2" DIA., INTERMEDIATE METAL	FOOT	160
* 81603000	UNIT DUCT, 600V, 2-1C NO.8, 1/C NO.8 GROUND, (XLP-TYPE USE), 3/4" DIA. POLYETHYLENE	FOOT	360
* 81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	200
* 82102250	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 250 WATT	EACH	3
* 82500605	LIGHTING CONTROLLER PHOTOCCELL RELAY	EACH	1
* 83008600	LIGHT POLE, ALUMINUM, 40 FT. M.H., 15 FT. MAST ARM	EACH	3
* 83600300	LIGHT POLE FOUNDATION, 30" DIAMETER	FOOT	18
* 83800650	BREAKAWAY DEVICE, COUPLING, WITH STAINLESS STEEL SCREEN	EACH	12
* A2002914	TREE, CELTIS OCCIDENTALIS (COMMON HACKBERRY), 1-3/4" CALIPER, BALLED AND BURLAPPED	EACH	14
* A2006714	TREE, QUERCUS MACROCARPA (BUR OAK), 1-3/4" CALIPER, BALLED AND BURLAPPED	EACH	20
* X XX005938	SOLAR-POWERED FLASHING BEACON ASSEMBLY (COMPLETE)	EACH	2
X XX005896	CONCRETE PAD REMOVAL	SQ FT	451
X X0323653	REMOVE AND RELOCATE INFORMATION KIOSK	EACH	1
X X0325519	DRAIN FOR AGGREGATE BASE COURSE	SQ YD	143
X X0712400	TEMPORARY PAVEMENT	SQ YD	3759
X X0919000	TEMPORARY PAVEMENT REMOVAL	SQ YD	3759
X X4402200	PAVEMENT REMOVAL (CONCRETE)	SQ YD	214
X Z0013798	CONSTRUCTION LAYOUT	L SUM	1
X Z0018700	DRAINAGE STRUCTURE TO BE REMOVED	EACH	1
* X Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2
X Z0055100	RUMBLE RESURFACING	SQ YD	100
* SPECIALTY ITEMS			
X SEE SPECIAL PROVISIONS			