SCHEDULE OF QUANTITIES

20100110 TREE REMOVAL (6 TO 15 UNITS DIAMETER)

UNIT (IN)	LOCATION	
12	580+57	54 LT
12	580+57	54 LT
14	580+57	54 LT
12	580+72	72 RT
13	580+72	72 RT
15	580+72	72 RT
10	1377+80	68 LT
11	1377+80	68 LT
13	1377+80	68 LT
6	1377+95	68 LT
13	1377+95	68 LT
9	1377+95	68 LT
8	1377+95	68 LT
12	1380+12	71 LT
160	**TOTAL**	

20100210 TREE REMOVAL (OVER 15 UNITS DIAMETER)

UNIT (IN)	LOCATION	
39	1375+88	33 RT
49	1375+93	35 RT
23	1376+29	10 RT
29	1376+36	2 RT
17	1376+64	9 LT
18	1377+95	68 LT
16	1378+97	34 LT
21	1378+47	45 LT
19.5	1378+73	54 LT
21	1378+47	24 LT
26	1379+17	36 LT
16	1379+37	36 LT
20.5	1379+56	39 LT
16.5	1379+73	40 LT
16	1379+92	38 LT
19	1380+10	54 LT
18	580+90	30 LT
18	580+90	35 LT
17	580+72	72 RT
17	580+72	72 RT
437	**TOTAL**	

28000300 TEMPORARY DITCH CHECKS

EACH	LOCATION
1	577+00 LT
1	577+50 LT
1	578+00 RT, LT
1	578+50 LT
2	579+00 RT, LT
2	579+50 RT, LT
2	580+00 RT, LT
2	580+50 RT, LT
1	581+00 LT
1	581+50 LT
1	582+00 LT
1	582+50 LT
1	583+00 LT
1	583+50 LT
1	584+00 LT
1	584+50 LT
1	585+00 LT
1	587+00 LT
1	587+50 LT
1	589+00 RT
1	589+50 RT
1	590+00 RT
1	590+50 RT
1	591+00 RT
1	591+50 RT
1	592+50 LT
1	594+00 LT
1	594+50 LT
1	595+00 LT
1	595+50 LT
1	596+00 LT
1	596+50 LT
1	1375+00 RT
1	1376+00 RT
2	1376+50 RT, LT
2	1377+00 RT, LT
2	1377+50 RT, LT
3	1378+00 RT, LT
3	1378+50 RT, LT
3	1379+00 RT, LT
3	1379+50 RT, LT
1	1380+00 RT
1	1380+50 RT
3	1381+00 RT, LT
2	1381+50 LT
2	1382+50 LT
2	1383+00 LT
2	1383+50 LT
2	1384+00 LT
2	1384+50 LT
1	1385+00 LT
1	1385+50 LT
1	1386+00 LT
1	1386+50 LT
1	1387+00 LT
1	1387+50 LT
1	1388+00 LT
1	1389+50 LT
81	**TOTAL**

28000400 PERIMETER EROSION BARRIER

FOOT	LOCATION
2174	US 20 - 575+62 - 596+80 RT
964	US 20 - 575+62 - 586+10 LT
794	US 20 - 586+10 - 595+80 LT
809	IL 84 - 1375+50 - 1383+00 RT
1483	IL 84 - 1375+50 - 1390+00 LT
6224	**TOTAL**

28000500 INLET AND PIPE PROTECTION

EACH	LOCATION
1	US 20 - 576+12 RT
1	US 20 - 580+80 LT
1	US 20 - 591+25 LT
1	US 20 - 591+80 RT
1	US 20 - 593+25 LT
2	IL 84 - 1375+50 RT, LT
1	IL 84 - 1376+80 LT
2	IL 84 - 1380+10 LT
2	IL 84 - 1382+00 LT
1	IL 84 - 1388+40 LT
13	**TOTAL**

35101400 AGGREGATE BASE COURSE, TYPE B

TON	LOCATION	
	US 20	
475	575+62 - 596+83 RT	4" UNDER SHOULDER
401	575+62 - 596+83 LT	4" UNDER SHOULDER
	IL 84	
112	1347+66 - 1383+00 RT	4" UNDER SHOULDER
211	1347+66 - 1383+00 LT	4" UNDER SHOULDER
	ENTRANCES	
129	1380+41 LT	8" UNDER FIELD ENTRANCE
40	1388+60 LT	8" UNDER FIELD ENTRANCE
61	576+07 LT	8" UNDER FIELD ENTRANCE
55	576+01 RT	8" UNDER PRIVATE ENTRANCE
49	591+69 LT	8" UNDER COMMERCIAL ENTRANCE
115	592+01 RT	8" UNDER FIELD ENTRANCE
25	593+49 LT	8" UNDER PRIVATE ENTRANCE
1673	**TOTAL**	

40600982 HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT

SQ YD	LOCATION
80	US 20 - 575+62
80	US 20 - 596+83
160	**TOTAL**

40600990 TEMPORARY RAMP

SQ YD	LOCATION
22	US 20 - 575+62
22	US 20 - 596+83
44	**TOTAL**

44000100 PAVEMENT REMOVAL

SQ YD	LOCATION	
3599	IL 84 PAVEMENT	IL 1383+00 SOUTH TO US 20 590+82
1458	1379+63 TO 582+39	IL 84 (SB) CONNECTOR TO US 20 (WB)
157	1377+55	NORTH MOST CONNECTING ROAD
893	1376+00	CONNECTING ROAD
296	587+48	SOUT MOST CONNECTING ROAD
6403	**TOTAL**	

44000200 DRIVEWAY PAVEMENT REMOVAL

SQ YD	LOCATION
40	590+50 LT
33	591+60 LT
24	592+30 LT
97	**TOTAL**

44201383 CLASS C PATCHES, TYPE IV, 12 INCH

SQ YD	LOCATION
27	US 20 - 580+80
27	**TOTAL**

44300200 STRIP REFLECTIVE CRACK CONTROL TREATMENT

FOOT	LOCATION
362	586+88 - 590+50 LT
1400	577+00 - 591+00 RT
1762	**TOTAL**

50105200 REMOVE EXISTING CULVERTS

EACH	LOCATION	
1	US 20 - 580+80	80' - 66" CMP
1	IL 84 - 1381+98	52' - 2'x1.5' BOX
2	**TOTAL**	

542A0229 PIPE CULVERTS, CLASS A, TYPE 1 24"

FOOT	LOCATION
105	IL 84 - 1375+50
70	IL 84 - 1381+98
175	**TOTAL**

542A1081 PIPE CULVERTS, CLASS A, TYPE 2 36"

FOOT	LOCATION
116	US 20 - 580+77
116	**TOTAL**

542D0220 PIPE CULVERTS, CLASS D, TYPE 1 15"

FOOT	LOCATION
50	IL 84 - 1380+41 LT
50	IL 84 - 1388+60 LT
45	US 20 - 576+01 RT
70	US 20 - 591+69 LT
50	US 20 - 592+01 RT
50	US 20 - 593+49 LT
315	**TOTAL**

5421D015 PIPE CULVERTS, CLASS D, TYPE 1 15" (TEMPORARY)

FOOT	LOCATION
50	IL 84 - 1380+41, 35' LT STAGE 3
50	IL 84 - 1380+41, 100' LT STAGE 3
100	**TOTAL**

5421D024 PIPE CULVERTS, CLASS D, TYPE 1 24" (TEMPORARY)

FOOT	LOCATION
80	IL 84 - 1375+50 LT STAGE 1
50	IL 84 - 1381+98 LT STAGE 3
70	2376+48 TEMPORARY PAVEMENT
200	**TOTAL**

54213450 END SECTIONS 15"

EACH	LOCATION
2	IL 84 - 1380+41 LT
2	IL 84 - 1380+41, 35' LT STAGE 3
2	IL 84 - 1380+41, 100' LT STAGE 3
2	IL 84 - 1388+60 LT
2	US 20 - 576+01 RT
2	US 20 - 591+69 LT
2	US 20 - 592+01 RT
2	US 20 - 593+49 LT
16	**TOTAL**

54213669 PRECAST REIN. CONC. FLARED END SECTIONS 24"

EACH	LOCATION
2	IL 84 - 1375+50 RT, LT
2	IL 84 - 1381+98 RT, LT
4	**TOTAL**

54213681 PRECAST REIN. CONC. FLARED END SECTIONS 36"

EACH	LOCATION
2	US 20 - 580+77 LT, RT
2	**TOTAL**

60221100 MANHOLES, TY. A, 5'-DIA, TY. 1 FRAME, CLOSED LID

EACH	LOCATION
1	US 20 - 580+83 RT
1	**TOTAL**

60608600 COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.06

FOOT	LOCATION	
51	585+66 - 585+85	ISLAND
51	**TOTAL**	

60618300 CONCRETE MEDIAN SURFACE, 4 INCH

SQ FT	LOCATION	
157	585+66 - 585+85	ISLAND
157	**TOTAL**	

63500105 DELINEATORS

EACH	LOCATION
2	US 20 - 580+77 LT, RT
2	IL 84 - 1381+98 LT, RT
2	IL 84 - 1375+50 LT, RT
6	**TOTAL**