

# SUMMARY OF QUANTITIES

URBAN  
90% FED / 10% STATE  
HSIP

CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY	SFTY-4A	Y031-1F
20200100	EARTH EXCAVATION	CU YD	844	844	
20800150	TRENCH BACKFILL	CU YD	110	110	
25200110	SODDING, SALT TOLERANT	SQ YD	863	863	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	200	200	
28000500	INLET AND PIPE PROTECTION	EACH	3	3	
31200100	STABILIZED SUB-BASE 4"	SQ YD	2,231	2,231	
40600735	POLYMERIZED LEVELING BINDER, (HAND METHOD), N70	TON	15	15	
40600837	POLYMERIZED LEVELING BINDER, (MACHINE METHOD), N70	TON	225	225	
40600990	TEMPORARY RAMP	SQ YD	151	151	
40603540	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	270	270	
42100100	CONTINUOUSLY REINFORCED PORTLAND CEMENT CONCRETE PAVEMENT 8"	SQ YD	1,382	1,382	
42100700	PAVEMENT REINFORCEMENT 8"	SQ YD	1,382	1,382	
44000100	PAVEMENT REMOVAL	SQ YD	72	72	
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2-1/2"	SQ YD	2,322	2,322	
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	2,005	2,005	
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	1,864	1,864	
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	69	69	
55100500	STORM SEWER REMOVAL 12"	FOOT	30	30	
60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1	
60242801	INLETS, SPECIAL, NO.5	EACH	2	2	
60500060	REMOVING INLETS	EACH	8	8	
60603500	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.06	FOOT	409	409	
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	93	93	
60619124	CONCRETE MEDIAN, TYPE SB-6 (SPECIAL)	SQ FT	6594	6,594	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	3	

\* SPECIALTY ITEMS