

70300520 PAVEMENT MARKING TAPE, TYPE III 4"

FOOT	LOCATION	OFFSET	REMARKS
600	I-88 WEST BOUND EDGE LINE	RT	PER STANDARD 701451 (SPECIAL)
1300	I-39 LANE CLOSURE	RT	PER STANDARD 701401
1900	TOTAL		

70301000 WORK ZONE PAVEMENT MARKING REMOVAL

SQ.FT	LOCATION	OFFSET	REMARKS
200.0	I-88 WEST BOUND LANE	RT	PER STANDARD 701451 (SPECIAL)
433.3	I-39 LANE CLOSURE	RT	PER STANDARD 701401
633.3	TOTAL		

78000200 THERMOPLASTIC PAVEMENT MARKING - LINE 4"

FOOT	LOCATION	OFFSET	REMARKS
883	1428+13 TO 1436+96	RT	INTERSTATE WHITE EDGE LINE
869	38+66 TO 47+35	LT	YELLOW
3146	38+66 TO 70+12	RT	WHITE
4898	TOTAL		

78000500 THERMOPLASTIC PAVEMENT MARKING - LINE 8"

FOOT	LOCATION	OFFSET	REMARKS
729	47+35 TO 54+64	LT	WHITE
729	TOTAL		

78000600 THERMOPLASTIC PAVEMENT MARKING - LINE 12"

FOOT	LOCATION	OFFSET	REMARKS
138	46+00 TO 47+35	LT	RAMP GORE AREA (SEE PLAN SHEET DETAIL)
138	TOTAL		

78100100 RAISED REFLECTIVE PAVEMENT MARKER

EACH	LOCATION	OFFSET	REMARKS
6	38+96 TO 40+56	LT & RT	80' SPACING - 3 AMBER & 3 CRYSTAL
17	40+96 TO 47+28	LT	40' SPACING - AMBER
20	40+96 TO 48+56	RT	40' SPACING - CRYSTAL
27	49+36 TO 70+08	RT	80' SPACING - CRYSTAL
70	TOTAL		

78300100 PAVEMENT MARKING REMOVAL

SQ.FT	LOCATION	OFFSET	REMARKS
812.9	1428+13 TO 1452+54	RT	INTERSTATE EDGE LINE
812.9	TOTAL		

FILE NAME =	USER NAME = stringerjm	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES				F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
ct:\pw_work\PWIDOT\STRINGERJM\dms84027\200309-sht-schedule.dgn	PLOT SCALE = 50.0000' / IN.	DRAWN -	REVISED -		39	(141-1M-1)	OGLE	82	19				
PLOT DATE = Fri Jan 23 11:31:48 2009	DATE -	CHECKED -	REVISED -		SCALE:	SHEET NO. 19 OF 82 SHEETS	STA.	TO STA.	CONTRACT NO. 64E60				
					ILLINOIS FED. AID PROJECT								