

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

ROUTE NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
IL 75	(77BRIM)	WINNEBAGO	13	2
FED. ROAD DIST. NO. 7		ILLINOIS	FED. AID PROJECT-	
CONTRACT 6467				

CODE NO.	ITEM	UNIT	QUANTITY		100% STATE TOTAL
			X081-2A BRIDGE	I000-2A ROADWAY	
42001300	PROTECTIVE COAT	SQ YD	554		554
50102400	CONCRETE REMOVAL	CU. YD.	48		48
50300255	CONCRETE SUPERSTRUCTURE	CU. YD.	48		48
52000110	PREFORMED JOINT STRIP SEAL	FOOT	114		114
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	13,940		13,940
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	175	27	202
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ. YD.	1,975		1,975
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON		28	28
58100200	WATERPROOFING MEMBRANE SYSTEM	SQ. YD.	1,975		1,975
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO		4	4
67100100	MOBILIZATION	L SUM		1	1
70100405	TRAFFIC CONTROL AND PROTECTION STANDARD 701321	EACH		1	1
70100450	TRAFFIC CONTROL AND PROTECTION STANDARD 701201	EACH		1	1
70102640	TRAFFIC CONTROL AND PROTECTION STANDARD 701801	EACH		1	1
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH		1	1
70300220	TEMPORARY PAVEMENT MARKING-LINE 4"	FOOT		3,750	3,750
70300280	TEMPORARY PAVEMENT MARKING-LINE 24"	FOOT		50	50
* 78001110	PAINT PAVEMENT MARKING LINE 4"	FOOT		2,250	2,250
70300100	SHORT TERM PAVEMENT MARKING	FOOT		2,250	2,250
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	FOOT		750	750
78300100	PAVEMENT MARKING REMOVAL	SQ. FT.		553	553
70400100	TEMPORARY CONCRETE BARRIER	FOOT		770	770
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT		770	770
50800515	BAR SPLICERS	EACH	50		50
Z0016200	DECK SLAB REPAIR (PARTIAL DEPTH)	SQ. YD.	445		445
Z0029100	GRINDING BITUMINOUS SURFACE CONCRETE	SQ. YD.		290	290
Z0030240	IMPACT ATTENUATORS, TEMPORARY (NON- REDIRECTIVE), TEST LEVEL 2	EACH		2	2
Z0030340	IMPACT ATTENUATORS, RELOCATE (NON- REDIRECTIVE), TEST LEVEL 2	EACH		2	2
X0325305	STRUCTURAL REPAIR OF CONCRETE (DEPTH LESS THAN OR EQUAL TO 5 INCHES)	SQ. FT.	3,550		3,550
50300530	FLOOR DRAIN EXTENSIONS	EACH	72		72
X0321468	PLUG EXISTING DECK DRAINS	EACH	112		112

* SPECIALTY ITEM

DESIGNED	M.H.
CHECKED	P.B.
DRAWN	C.L.
CHECKED	M.H./P.B.

SUMMARY OF QUANTITIES

IL ROUTE 75 OVER ROCK RIVER
FAP ROUTE 505 (IL 75), SECTION (77BRIM)
WINNEBAGO COUNTY
STATION 206+00
STRUCTURE NO. 101-0109

SCALE: _____ DATE: January, 2009

Soodan Soodan & Associates, Inc.
100 North LaSalle Street, Suite 1800
Chicago, Illinois 60602