

Item No.	Item	Unit	Total	1000 ROADWAY	Y031-IF TRAFFIC SIGNALS US 45/52	Y031-IF TRAFFIC SIGNALS EDGEMERE DRIVE	Y031-IF TRAFFIC SIGNALS FIRE DEPT.	Y031-IF TRAFFIC SIGNALS WASHINGTON/MOONEY	SFTY-1B SIDEWALK	SFTY-2A BRIDGE RAIL
* 87800150	CONCRETE FOUNDATION, TYPE C	FOOT	3.5	--	--	--	--	3.5	--	--
* 87800415	CONCRETE FOUNDATION, TYPE E, 36 INCH DIAMETER	FOOT	57	--	--	--	10	47	--	--
* 87900200	DRILL EXISTING HANDHOLE	EACH	47	--	14	--	--	33	--	--
* 88030030	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, SPAN WIRE MOUNTED	EACH	1	--	--	1	--	--	--	--
* 88030120	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, SPAN WIRE MOUNTED	EACH	1	--	--	1	--	--	--	--
* 88040070	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	2	--	--	--	--	2	--	--
* 88040090	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, MAST ARM MOUNTED	EACH	14	--	--	--	2	12	--	--
* 88040150	SIGNAL HEAD, POLYCARBONATE, LED 1-FACE, 5-SECTION, BRACKET MOUNTED	EACH	1	--	--	1	--	--	--	--
* 88200410	TRAFFIC SIGNAL BACKPLATE, LOUVERED, FORMED PLASTIC	EACH	23	--	--	3	2	18	--	--
* 88500100	INDUCTIVE LOOP DETECTOR	EACH	16	--	5	--	--	11	--	--
* 88600100	DETECTOR LOOP, TYPE I	FOOT	2712	--	944	--	--	1768	--	--
* 88700200	LIGHT DETECTOR	EACH	3	--	--	--	1	2	--	--
* 88700300	LIGHT DETECTOR AMPLIFIER	EACH	2	--	--	--	1	1	--	--
* 89500100	RELOCATE EXISTING SIGNAL HEAD	EACH	3	--	--	3	--	--	--	--
* 89500300	RELOCATE EXISTING ILLUMINATED SIGN	EACH	2	--	--	--	2	--	--	--
* 89502210	MODIFY EXISTING CONTROLLER CABINET	EACH	2	--	--	1	1	--	--	--
* 89502300	REMOVE ELECTRIC CABLE FROM CONDUIT	FOOT	8763	--	--	--	207	8556	--	--
* 89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	3	--	--	1	1	1	--	--
* 89502385	REMOVE EXISTING CONCRETE FOUNDATION	EACH	9	--	--	--	2	7	--	--
X0322127	STORM SEWER (WATER MAIN REQUIREMENTS), 30"	FOOT	124	124	--	--	--	--	--	--
X5510100	STORM SEWER REMOVAL	FOOT	479	479	--	--	--	--	--	--
* X8730027	ELECTRIC CABLE IN CONDUIT, GROUNDING, NO. 6 1C	FOOT	1042.5	--	--	--	288.5	754	--	--
* X8808020	OPTICALLY PROGRAMMED SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, MAST ARM MOUNTED	EACH	4	--	--	--	--	4	--	--
* X8860100	LOOP DETECTOR TESTING	EACH	1	--	1	--	--	--	--	--
* X8950115	RELOCATE LIGHT DETECTOR	EACH	2	--	--	--	--	2	--	--
* X8950120	RELOCATE LIGHT DETECTOR AMPLIFIER	EACH	2	--	--	--	--	2	--	--
* X8730430	ELECTRIC CABLE IN CONDUIT, COMMUNICATION *20 3/C	FOOT	1130	--	--	--	179.5	950.5	--	--
724-00710	RELOCATE SIGN PANEL - TYPE I	EACH	1	--	--	1	--	--	--	--
60250620	CATCH BASIN TO BE ADJUSTED WITH NEW TYPE 3V FRAME AND GRATE	EACH	1	1	--	--	--	--	--	--
60207115	CATCH BASIN TYPE C, TYPE 3V FRAME AND GRATE	EACH	3	3	--	--	--	--	--	--
X6020089	MANHOLES, TYPE A, 8' DIAMETER, TYPE I FRAME, AND OPEN LID	EACH	1	1	--	--	--	--	--	--
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1	--	--	--	--	--	--
Z0017100	DOWEL BARS	EACH	6480	6480	--	--	--	--	--	--
Z0018700	DRAINAGE STRUCTURE TO BE REMOVED	EACH	2	2	--	--	--	--	--	--
Z0075300	TIE BARS	EACH	775	775	--	--	--	--	--	--
+ Z0076000	TRAINEES	HOURL	2,000	2,000	--	--	--	--	--	--

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	KANKAKEE	109	7
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

* FAU ROUTE 6176 (ARMOUR ROAD)
** SECTION (79)W&RS & 140RS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
FAU ROUTE 6176 (ARMOUR ROAD)
SEC (79)W&RS & 140RS
KANKAKEE COUNTY

SCALE: VERT. _____
 HORIZ. _____
DATE: _____

DRAWN BY: KKP
CHECKED BY: JKC

PLOT DATE * 12/06
 FILE NAME * 20-0355-00-00
 USER NAME * JKR

* SPECIALTY ITEM + Y080
100% STATE NON-PARTICIPATING