SUMMARY OF QUANTITIES

CODE NO.	ITEM	100% STATE SAFETY-2A WOODFORD COUNTY UNIT	RURAL	TOTAL
50102400	CONCRETE REMOVAL	CUYD	0.7	0.7
50300255	CONCRETE SUPERSTRUCTURE	CUYD	0.7	0.7
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	5,120	5,120
50501110	STRUCTURAL STEEL REMOVAL	POUND	5,185	5,185
67100100	MOBILIZATION	LSUM	1	1
70100100	TRAFFIC CONTROL AND PROTECTION, STANDARD 701316	EACH	1	1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	LSUM	1	1
70100700	TRAFFIC CONTROL AND PROTECTION, STANDARD 701406	LSUM	1	1
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1	1
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	1	1
X0325778	SOLUBLE REACTIVE SILICATE CONCRETE TREATMENT	SQYD	635	635
Z0003600	BEAM STRAIGHTENING	LSUM	1	1
Z0073300	TEMPORARY SHORING AND CRIBBING	LSUM	1	1
Z0073351	TEMPORARY SLAB SUPPORT SYSTEM	LSUM	1	1

SN. 102-0034
TR134over I-74

FILE NAME = D468854-sht-cover.dgn	USER NAME = jonesce	DESIGNED - CEJ	REVISED - ---
		DRAWN - CEJ	REVISED - ---
	PLOT SCALE = 184.4291 ' / IN.	CHECKED - ---	REVISED - ---
= Emergency Bridge Repair	PLOT DATE = 1/15/2009	DATE - --------	REVISED - ---

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: _____ | SHEET NO. __ OF ___ SHEETS | STA. _____ TO STA. _____

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
74	(X3-17HBI-2	WOODFORD	11	3
BEAM REPAIRS		CONTRACT NO. 68854		
FED. ROAD DIST. NO. 4	ILLINOIS	FED. AID PROJECT		