

# SCHEDULE OF QUANTITIES

## SRS CONCRETE TREATMENT

LOCATION	SQYD
DECK SURFACE	590
VERTICAL SIDES	45
TOTAL	635

## TRAFFIC CONTROL

LOCATION STA. TO STA.	TEMP. BR. TRAF. SIGNALS (EA)	T.C.&P. STANDARD 701406 (LSUM)	T.C.&P. STANDARD 701316 (EACH)	T.C.&P. STANDARD 701201 (LSUM)	CHANGEABLE MESSAGE SIGN (CALM)
T.R.134 DECK I-74	1	1	1	1	1
TOTAL	1	1	1	1	1

## STEEL BEAM REPAIRS

CONCRETE REMOVAL	
SOUTH HALF OF SPAN 2	CUYD
Span 2	TOTAL 0.7
CONCRETE SUPERSTRUCTURE	
SOUTH HALF OF SPAN 2	CUYD
Span 2	TOTAL 0.7
FURNISHING & ERECTING STRUCTURAL STEEL	
SPAN 2	PD
Span 1 & 2 Replacement Area	TOTAL 5,120
STRUCTURAL STEEL REMOVAL	
SPAN 2	PD
Spans 1 & 2 Designated Beams	TOTAL 5,185
TEMPORARY SLAB SUPPORT SYSTEM	
BEAM STRAIGHTENING DETAILS	LSUM
Pier 1	TOTAL 1
BEAM STRAIGHTENING	
SPAN 2, BEAM 5	LSUM
Span 2	TOTAL 1
TEMPORARY SHORING & CRIBBING	
BEAM STRAIGHTENING DETAILS	LSUM
Jobsite Deck Support	TOTAL 1

SN. 102-0034  
TR134over I-74

FILE NAME = D468854-sht-cover.dgn	USER NAME = jonesce	DESIGNED - CEJ	REVISED - ---	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES	F.A.I. RTE. 74	SECTION (X3-17HB)I-2	COUNTY WOODFORD	TOTAL SHEETS 11	SHEET NO. 5
PLOT SCALE = 1/8" = 1'-0"	PLOT DATE = 1/15/2009	DRAWN - CEJ	REVISIONS - ---		SCALE: _____	SHEET NO. ___ OF ___ SHEETS		STA. _____ TO STA. _____		FED. ROAD DIST. NO. 4 ILLINOIS FED. AID PROJECT
		CHECKED - ---	REVISIONS - ---			BEAM REPAIRS		CONTRACT NO. 68854		
		DATE - -----	REVISIONS - ---							