

LOCATION OF WORK:

MCLEAN COUNTY
 STRUCTURE
 IMPROVEMENTS
 S.N. 057-0202
 FAS 676 (US 150)
 STA. 189+89.00
 100% STATE
 STA. 196+46.00

CONSTRUCTION TYPE CODE:

SFTY-2A
 TOTAL

CODE NO	ITEM	UNIT	QUANTITY
63200310	GUARDRAIL REMOVAL	FOOT	60.0
67100100	MOBILIZATION	L SUM	1.0
70100320	TRAFFIC CONTROL AND PROTECTION, STANDARD 701422	L SUM	1.0
70100325	TRAFFIC CONTROL AND PROTECTION, STANDARD 701423	EACH	2.0
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1.0
70400100	TEMPORARY CONCRETE BARRIER	FOOT	1,575.0
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	1,425.0
X0325305	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	657.0
* X7200201	WIDTH RESTRICTION SIGNING	L SUM	1.0
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2.0
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2.0
X7015005	CHANGEABLE MESSAGE SIGN	CAL DA	28.0
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1.0
*	SPECIALTY ITEMS		

FILE NAME :	USER NAME = shorerjm	DESIGNED - JMS	REVISED -
g:\pr_work\phidot\shorerjm\dms83928\7071Summary.dgn	DRAWN - JMS	REVISED -	
PLOT SCALE = 100.0000' / IN.	CHECKED - JMS	REVISED -	
PLOT DATE = 1/30/2009	DATE - 090308	REVISED -	

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: N/A SHEET NO. 1 OF 1 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
676	(9-1)B-JR	MCLEAN	17	4A
CONTRACT NO. 70731				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				