

100% FED.

CONSTRUCTION TYPE CODE	
I-57 STA 841+07.00 TO STA 841+64.63	I-57 STA 900+52.80 TO STA 1386+91.00
STA. EQUATION: 841+64.63 (BK)= 813+20.49 (AH)	
STA 813+20.49 TO STA 900+52.80	
URBAN	RURAL

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	TOTAL QUANTITIES	CONSTRUCTION TYPE CODE	
				I000	I000
X0326340	PIPE UNDERDRAIN BACKFILL, SPECIAL	TON	15836	1828.9	14007.1
20200100	EARTH EXCAVATION	CU YD	322	101	221
20200600	EXCAVATING AND GRADING EXISTING SHOULDER	UNIT	2045	90.8	1954.2
20300100	CHANNEL EXCAVATION	CU YD	1373		1373
20400800	FURNISHED EXCAVATION	CU YD	1394	186	1208
25000200	SEEDING, CLASS 2	ACRE	3.1	0.7	2.4
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	279	63	216
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	279	63	216
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	279	63	216
25100115	MULCH, METHOD 2	ACRE	3.1	0.7	2.4
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	310	70	240
28000500	INLET AND PIPE PROTECTION	EACH	3		3
28100809	STONE DUMPED RIPRAP, CLASS A5	TON	1567		1567
31100300	SUB-BASE GRANULAR MATERIAL, TYPE A 4"	SQ YD	1980		1980
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	51481	7446.1	44034.9
40600300	AGGREGATE (PRIME COAT)	TON	1029	149	880
40600895	CONSTRUCTING TEST STRIP	EACH	2	1	1
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	220		220
40600990	TEMPORARY RAMP	SQ YD	171	85.5	85.5
40603245	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N105	TON	43847	8322.6	35524.4
40603550	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N105	TON	25606	3861.5	21744.5
44000153	HOT-MIX ASPHALT SURFACE REMOVAL, 1"	SQ YD	51987		51987
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	15777	5070.8	10706.2
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	1223		1223
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	683		683
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SQ YD	1529		1529

X0326446	HOT-MIX ASPHALT SHOULDER PLUG, 7 1/2"	FOOT	117,221	19,457.3	97,763.7
44000173	HOT-MIX ASPHALT SURFACE REMOVAL, 6"	SQ YD	47,410	7,446.3	39,963.7
48203021	HOT-MIX ASPHALT SHOULDERS, 6"	SQ YD	47,410	7,446.3	39,963.7
* 78003130	PRE-FORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 6"	FOOT	28,463	5,480	23,183
* 78003140	PERFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 8"	FOOT	1,800	944	856
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DAY	140	23	117

100% FED.

CONSTRUCTION TYPE CODE	
I-57 STA 841+07.00 TO STA 841+64.63	I-57 STA 900+52.80 TO STA 1386+91.00
STA. EQUATION: 841+64.63 (BK)= 813+20.49 (AH)	
STA 813+20.49 TO STA 900+52.80	
URBAN	RURAL

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	TOTAL QUANTITIES	CONSTRUCTION TYPE CODE	
				I000	I000
44000161	HOT-MIX ASPHALT SURFACE REMOVAL, 3"	SQ YD	1209	1209	
44000162	HOT-MIX ASPHALT SURFACE REMOVAL, 3 1/4"	SQ YD	63955		63955
44000166	HOT-MIX ASPHALT SURFACE REMOVAL, 4 1/4"	SQ YD	917		917
44000168	HOT-MIX ASPHALT SURFACE REMOVAL, 4 3/4"	SQ YD	80863	12571.1	68291.9
44000170	HOT-MIX ASPHALT SURFACE REMOVAL, 5 1/4"	SQ YD	907	907	
44000177	HOT-MIX ASPHALT SURFACE REMOVAL, 7"	SQ YD	223844	43000.6	180843.4
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	10939	2600	8339
44004250	PAVED SHOULDER REMOVAL	SQ YD	83158	10142.9	73015.1
44200513	CLASS A PATCHES, TYPE I, 7 INCH	SQ YD	164	4	160
44200517	CLASS A PATCHES, TYPE II, 7 INCH	SQ YD	1973	432.7	1540.3
44200521	CLASS A PATCHES, TYPE III, 7 INCH	SQ YD	462	132.7	329.3
44200523	CLASS A PATCHES, TYPE IV, 7 INCH	SQ YD	324	140	184
44200559	CLASS A PATCHES, TYPE IV, 10 INCH	SQ YD	3520		3520
44212900	PAVEMENT PATCHING (PARTIAL DEPTH)	SQ YD	2000		2000
44213000	PATCHING REINFORCEMENT	SQ YD	6500	720	5780
44213200	SAW CUTS	FOOT	24266	4014.5	20251.5
48101200	AGGREGATE SHOULDERS, TYPE B	TON	6079	1002.5	5076.5
48203034	HOT-MIX ASPHALT SHOULDERS, 9 1/4"	SQ YD	83158	10143	73015
48203037	HOT-MIX ASPHALT SHOULDERS, 10"	SQ YD	1320		1320
48203100	HOT-MIX ASPHALT SHOULDERS	TON	18898	3109	15789
50105220	PIPE CULVERT REMOVAL	FOOT	25		25
54246405	INLET BOX, STANDARD 542531	EACH	3		3
542A0229	PIPE CULVERTS, CLASS A, TYPE 1 24"	FOOT	130		130
60100060	CONCRETE HEADWALL FOR PIPE DRAINS	EACH	501	80	421
60100071	SHOULDER REMOVAL AND REPLACEMENT 9 1/4"	FOOT	205194	22928	182266
60100073	SHOULDER REMOVAL AND REPLACEMENT 10"	FOOT	2700		2700
20030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE) TEST LEVEL 3	EACH	4		4
20030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE) TEST LEVEL 3	EACH	4		4

*SPECIALTY ITEMS

Rev.