

RESURFACING SCHEDULE

STATION LOCATION	31101000 SUB-BASE GRANULAR MATERIAL, TYPE B TON	36650700 BASE COURSE WIDENING SQ YD	40600300 AGGREGATE (PRIME COAT) TON	40600982 HOT-MIX ASPHALT SURFACE REMOVAL-BUTT JOINT SQ YD	40600990 TEMPORARY RAMP SQ YD	40603085 HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70 TON	40603315 HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N70 TON	40600100 BITUMINOUS MATERIALS (PRIME COAT) GALLON	44000100 PAVEMENT REMOVAL SQ YD	44000198 HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH SQ YD	44004300 PAVEMENT BREAKING SQ YD	48203100 HOT-MIX ASPHALT SHOULDERS TON	#7000599 BASE COURSE WIDENING REMOVAL SQ YD
407+16.00 TO 407+94.50	83.3										226.9		
409+56.40 TO 410+57.00	126.0										290.7		
405+49.00 TO 408+36.50, RT.		108.8											
405+50.00 TO 407+94.50, LT.		105.1											
409+14.40 TO 413+02.65, RT.		143.7											
409+56.40 TO 413+11.50, LT.		157.6											
405+15.00 TO 408+45.21			0.8			358.0	93.0	168.4				128.0	
409+05.69 TO 412+65.00			0.9			390.0	110.0	203.9				131.0	
405+15.00 TO 405+45.00				86.7	86.7								
412+35.00 TO 412+65.00				86.7	86.7								
407+16.00 TO 407+29.33					38.6								
410+43.67 TO 410+57.00					38.4								
406+51.50 TO 406+70.00 (STAGE I)					34.9								
407+89.50 TO 407+94.50 (STAGE I)					9.4								
409+56.40 TO 409+61.40 (STAGE I)					9.4								
406+51.50 TO 406+70.00 (STAGE II)					34.9								
407+89.50 TO 407+94.50 (STAGE II)					9.4								
409+56.40 TO 409+61.40 (STAGE II)					9.4								
407+94.50 TO 408+56.02									177.6				
408+93.87 TO 409+56.40									180.6				
405+45.00 TO 407+16.00										494.0			
410+57.00 TO 412+35.00										514.2			
405+49.00 TO 408+36.50, RT.													103.8
409+14.40 TO 413+02.65, RT.													140.2
TOTALS	209.3	515.2	1.7	173.4	357.8	748.0	203.0	372.3	358.2	1008.2	517.6	259.0	244.0

EARTHWORK SCHEDULE

STATION LOCATION	20200100 EARTH EXCAVATION CU YD	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE (25%) CU YD	EARTH FILL CU YD	20400800 FURNISHED EXCAVATION CU YD
404+89.00 TO 408+56.02	166.7	125.0	933.0	-808.0
408+93.87 TO 412+65.00	85.6	64.2	537.8	-473.6
TOTALS	252.3	189.2	1470.8	-1281.6

BRIDGE APPROACH PAVEMENT SCHEDULE

STATION LOCATION	42001165 BRIDGE APPROACH PAVEMENT SQ YD	42001430 BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE) SQ YD
408+07.20 TO 408+37.20	125.4	
409+13.70 TO 409+43.70	125.4	
407+94.50 TO 408+07.20		52.0
409+43.70 TO 409+56.40		52.0
TOTALS	250.8	104.0

RIGHT-OF-WAY SCHEDULE

STATION LOCATION	66600105 FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS EACH	66700305 PERMANENT SURVEY MARKERS, TYPE II EACH
405+00.00, 40.0' LT.	1	
405+00.00, 40.0' RT.	1	
408+00.00, 70.0' LT.	1	
408+00.00, 75.0' RT.	1	
409+25.00, 70.0' LT.	1	
409+25.00, 75.0' RT.	1	
411+50.00, 40.0' LT.	1	
411+50.00, 40.0' RT.	1	
TO BE DETERMINED		1
TOTALS	8	1

SEEDING SCHEDULE

STATION LOCATION	25001000 SEEDING, CLASS 2 (SPECIAL) ACRE
405+15.00 TO 408+37.00, LT.	0.21
404+89.00 TO 408+17.00, RT	0.15
409+14.00 TO 412+65.00, LT	0.13
409+14.00 TO 412+65.00, RT	0.16
TOTALS	0.70