



PIPE DRAIN SCHEDULE		
STATION LOCATION	60109580 PIPE DRAINS, 4" LENGTH (FOOT)	INVERT ELEVATION
(A) SOUTH ABUTMENT, LT. SIDE	7.6	644.62
(B) SOUTH ABUTMENT, RT. SIDE	2.1	647.10
(C) NORTH ABUTMENT, LT. SIDE	28.4	648.00
(D) NORTH ABUTMENT, RT. SIDE	7.5	644.75
TOTALS	45.6	

RIPRAP SCHEDULE		
STATION LOCATION	28100107 STONE RIPRAP, CLASS A4 SQ YD	28200200 FILTER FABRIC SQ YD
408+00.50 TO 408+05.50, RT.	19.4	19.4
408+13.91 TO 408+18.91, LT.	19.4	19.4
409+32.00 TO 409+37.00, RT.	19.4	19.4
409+45.41 TO 409+50.41, LT.	19.4	19.4
TOTALS	77.6	77.6