

SUMMARY OF QUANTITIES			URBAN	100% STATE
CODE NO	ITEM	UNIT	TOTAL	CONSTRUCTION
			QUANTITIES	TYPE CODE
				Y007
21400100	GRADING AND SHAPING DITCHES	FOOT	110	110
25001000	SEEDING, CLASS 2 (SPECIAL)	ACRE	0.2	0.2
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	20	20
28000300	TEMPORARY DITCH CHECKS	EACH	3	3
28000500	INLET AND PIPE PROTECTION	EACH	3	3
28100107	STONE RIPRAP, CLASS A4	SQ YD	124	124
28200200	FILTER FABRIC	SQ YD	124	124
50104300	CONCRETE HEADWALL REMOVAL	CU YD	1	1
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	1	1
54213693	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 48"	EACH	2	2
542JA048	PIPE CULVERTS, CLASS A 48" (JACKED)	FOOT	172	172
550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	34	34
60240215	INLETS, TYPE B, TYPE 1 FRAME, CLOSED LID	EACH	1	1
67100100	MOBILIZATION	L SUM	1	1
70100310	TRAFFIC CONTROL AND PROTECTION, STANDARD 701421	L SUM	1	1
X0324079	EXISTING FIELD TILE REMOVAL	FOOT	32	32

FILE NAME =	USER NAME = #USER#	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES		F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
#FILE#		DRAWN -	REVISED -				323	(13X)I-3	MACON	7	3
	PLOT SCALE = #SCALE#	CHECKED -	REVISED -		SCALE: NA	SHEET NO. 1 OF 1 SHEETS	STA.	TO STA.	CONTRACT NO. 74342		
	PLOT DATE = #DATE#	DATE -	REVISED -		FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT						