

SUMMARY OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
310	60-15-2 60-15HB-2	MADISON	272	7
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
CONTRACT NO. 76624				

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE							
				URBAN							
				80% FEDERAL 20% STATE							
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	SEC 60-15-2		SEC 60-15HB-2					
				I000-2A	Y031-1F	X271-2A					
M4429400	SAW CUTS	METER	1646	1646							
M4430020	STRIP REFLECTIVE CRACK CONTROL TREATMENT	METER	2945	2945							
M4810150	AGGREGATE SHOULDERS, TYPE A 150MM	SQ M	2013	2013							
M4812200	AGGREGATE SHOULDERS, TYPE B 200MM	SQ M	155	155							
M4820600	HOT-MIX ASPHALT SHOULDERS, 200MM	SQ M	3110	3110							
M5010521	REMOVE EXISTING CULVERTS	METER	240	240							
M5020100	STRUCTURE EXCAVATION	CU M	664				664				
M5030290	FORM LINER TEXTURED SURFACE	SQ M	367				367				
M5030350	CONCRETE STRUCTURES	CU M	371.9				371.9				
M5030360	CONCRETE SUPERSTRUCTURE	CU M	452.4				452.4				
M5030390	BRIDGE DECK GROOVING	SQ M	1377				1377				
M5080105	REINFORCEMENT BARS	KG	1460	1460							
M5080205	REINFORCEMENT BARS, EPOXY COATED	KG	86120				86120				
M5110400	SLOPE WALL (SPECIAL)	SQ M	717				717				
M5120176	FURNISHING METAL SHELL PILES 356MM x 6.35MM	METER	1890.5				1890.5				
M5120335	DRIVING PILES	METER	1890.5				1890.5				
M5200225	PREFORMED JOINT STRIP SEAL	METER	50.5				50.5				
M5421210	PIPE CULVERTS, TYPE 1 RCCP 375MM	METER	8.5	8.5							
M5421240	PIPE CULVERTS, TYPE 1 RCCP 900MM	METER	27.5	27.5							
M5421250	PIPE CULVERTS, TYPE 1 RCCP 1200MM	METER	88	88							
M5421440	PIPE CULVERTS, TYPE 1, CORRUGATED STEEL OR ALUMINUM CULVERT PIPE 750MM	METER	11	11							
M5421835	PIPE CULVERTS, TYPE 1, REINFORCED CONCRETE, EQUIVALENT ROUND-SIZE 900MM	METER	30	30							
M5424155	PIPE CULVERTS, TYPE 2, REINFORCED CONCRETE, EQUIVALENT ROUND-SIZE 1500MM	METER	107	107							
M5429770	PIPE CULVERTS, TYPE 7 RCCP 1800MM	METER	116	116							
M5429900	CONCRETE HEADWALLS	CU M	31.4	31.4							
M542E116	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 375MM	EACH	2	2							
M542E144	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 900MM	EACH	2	2							
M542E544	PRECAST REINFORCED CONCRETE FLARED END SECTIONS, EQUIVALENT ROUND-SIZE 900MM	EACH	4	4							
M542G250	GRATING FOR CONCRETE FLARED END SECTION EQUIVALENT ROUND-SIZE 900MM	EACH	2	2							
M542H425	PIPE CULVERTS, CLASS D, TYPE 1 375MM	METER	187.5	187.5							
M542H430	PIPE CULVERTS, CLASS D, TYPE 1 450MM	METER	14	14							

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
 FAP 310 (IL 255)
 SECTION 60-15-2 & 60-15HB-2
 MADISON COUNTY
 DRAWN BY EBB
 CHECKED BY
 DATE

10/16/2008

\$FILE\$