

SUMMARY OF QUANTITIES

URBAN

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT	URBAN	ROAD	SIGNALS
			TOTAL QUANTITY	100% FEDERAL	100% FEDERAL
				J000	Y031-1F
20100500	TREE REMOVAL, ACRES	ACRE	0.3	0.3	0
20101100	TREE TRUNK PROTECTION	EACH	4	4	0
20200100	EARTH EXCAVATION	CU YD	14,594	14,594	0
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	4,053	4,053	0
20800150	TRENCH BACKFILL	CU YD	1,357	1,357	0
25000210	SEEDING, CLASS 2A	ACRE	2.7	2.7	0
25000300	SEEDING, CLASS 3	ACRE	1.1	1.1	0
25000314	SEEDING, CLASS 4B	ACRE	0.6	0.6	0
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	395	395	0
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	395	395	0
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	395	395	0
25100105	MULCH, METHOD 1	TON	28.4	28.4	0
25100630	EROSION CONTROL BLANKET	SQ YD	21,257	21,257	0
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	5,672	5,672	0
28000400	PERIMETER EROSION BARRIER	FOOT	3,295	3,295	0
28000500	INLET AND PIPE PROTECTION	EACH	4	4	0
28100127	STONE RIPRAP, CLASS B4	SQ YD	27	27	0
28200200	FILTER FABRIC	SO YD	27	27	0
31100910	SUB-BASE GRANULAR MATERIAL, TYPE A 12"	SQ YD	23,791	23,791	0
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	193	193	0

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT	URBAN	STATE ROAD	SIGNALS
			TOTAL QUANTITY	100% FEDERAL	100% FEDERAL
				J000	Y031-1F
40600100	BITUMINOUS MATERIALS PRIME COAT	GALLON	459	459	0
40600645	LEVELING BINDER (MACHINE METHOD), N90	TON	512	512	0
40603090	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N90	TON	1104	1104	0
40603520	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N90	TON	896	896	0
40603570	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "E", N90	TON	164	164	0
42000301	PORTLAND CEMENT CONCRETE PAVEMENT 8" (JOINTED)	SQ YD	7,458	7,458	0
42000401	PORTLAND CEMENT CONCRETE PAVEMENT 9" (JOINTED)	SQ YD	2,981	2,981	0
42000501	PORTLAND CEMENT CONCRETE PAVEMENT 10" (JOINTED)	SQ YD	10,092	10,092	0
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	17,440	17,440	0
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	98	98	0
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	74	74	0
44000100	PAVEMENT REMOVAL	SQ YD	15,794	15,794	0
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	5,873	5,873	0
44000166	HOT-MIX ASPHALT SURFACE REMOVAL, 4 1/4"	SQ YD	240	240	0
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	182	182	0
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	5,280	5,280	0
44000600	SIDEWALK REMOVAL	SQ FT	19,709	19,709	0
44003100	MEDIAN REMOVAL	SQ FT	4,013	4,013	0
44003510	MEDIAN REMOVAL PARTIAL DEPTH	SQ FT	1,513	1,513	0
44201722	CLASS D PATCHES, TYPE III, 6 1/2 INCH	SQ YD	40	40	0

* DESIGNATES A SPECIAL PROVISION

FILE NAME = r3nAsummary1.new.dgn	USER NAME = weaverlg	DESIGNED - A. PENICK	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES		F.A. RTE. 788	SECTION 520-2-2	COUNTY MADISON	TOTAL SHEETS 173	SHEET NO. 5	
	PLOT SCALE = \$SCALE\$	DRAWN - A. PENICK	REVISED -		SCALE:	SHEET NO. 1 OF 5 SHEETS	STA.	TO STA.	CONTRACT NO. 76633			
	PLOT DATE = 02/02/2009	CHECKED - A. FREY	REVISED -		FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT							
		DATE - 02/06/2009	REVISED -									