PAVEMENT MARKING SCHEDULE

SHEET DESCRIPTION	STATION	STATION	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	THERMOPLASTIC PAVEMENT MARKING - LINE 4"		THERMOPLASTIC PAVEMENT MARKING - LINE 12"		THERMOPLASTIC PAVEMENT MARKING LINE - 24"	POLYUREA PAVEMENT MARKING TYPE I - LETTERS AND SYMBOLS	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"		POLYUREA PAVEMENT MARKING TYPE I - LINE 8"	POLYUREA PAVEMENT MARKING TYPE I - LINE 12"		POLYUREA PAVEMENT MARKING TYPE I - LINE 24"	RAISED REFLECTIVE PAVEMENT MARKER		PRISMATIC CURB REFLECTOR		POLYUREA CURB MARKING
			SQ FT	FOOT		FOOT		FOOT	SQ FT	FOOT		FOOT	FOOT		FOOT	EACH		EACH		FOOT
ITEM DESCRIPTION:			WHITE	WHITE	YELLOW	WHITE	YELLOW	WHITE	WHITE	WHITE	YELLOW	WHITE	WHITE	YELLOW	WHITE	ONE-WAY		ONE-WAY		WHITE
																CRYSTAL	AMBER	CRYSTAL	AMBER	
RELOC. IL 3, BROADWAY / 2ND STREET,	775+10	792+15	13	541	1,337	59	67	0	243	2,467	5,181	450	811	201	220	56	102	57	143	67
ABBOTT STREET, HAMPDEN, RELOC. 4TH STREET			0	0	273	145	0	28	76	115	496	134	163	0	25	0	0	0	0	0
BROADWAY, 4TH ST. OVERLAYS			31	707	2,146	450	0	64	31	0	0	0	0	0	0	0	0	0	0	0
TOTALS:			44	1,248	3,756	654	67	92	350	2,582	5,677	584	974	201	245	56	102	57	143	67

ENTRANCE SCHEDULE

ENTRANCE DESCRIPTION	ALIGNMENT	STATION	AGGREGATE SURFACE COURSE, TYPE B	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH
			TON	SQ YD	SQ YD
OLD BROADWAY	RELOC. IL 3	788+08	0	0	0
ALLEY TURNAROUND #3	RELOC. IL 3	785+32	16	0	0
ALLEY TURNAROUND #4	RELOC. IL 3	782+79	15	0	0
ALLEY TURNAROUND #5	2ND ST.	6+74	9	0	0
ALLEY WIDENING NEAR 2ND ST.	2ND ST.	6+55	27	0	0
PRIVATE ENTRANCES IN 3RD ST. NORTH CUL-DE-SAC	3RD ST.	1+62 / 1+20	0	24	0
PRIVATE ENTRANCE ON 2ND ST.	2ND ST.	6+31	0	24	0
COMMERCIAL ENTRANCE ON BROADWAY AVE.	BROADWAY AVE.	13+17	0	0	74
ALLEY ON ABBOTT ST.	ABBOTT	31+51 LT & RT	0	23	0
ALLEY ON HAMPDEN ST. WEST	HAMPDEN	6+85	0	27	0
VARIOUS LOCATIONS (SEE GENERAL NOTE 18)			126	0	0
TOTALS:			193	98	74

EARTHWORK SCHEDULE

EARTHWORK LOCATION	EXCAVATION			EXCAVATION USED IN EMBANKMENT ADJUSTED FOR SHRINKAGE 25%			EMBANKMENT			EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)		
	STAGE 1	STAGE 2	STAGE 3	STAGE 1	STAGE 2	STAGE 3	STAGE 1	STAGE 2	STAGE 3	STAGE 1	STAGE 2	STAGE 3
	CU YD	CU YD	CU YD	CU YD	CU YD	CU YD	CU YD	CU YD	CU YD	CU YD	CU YD	CU YD
RELOC. IL 3	3,320	486	0	2,490	364	0	2,505	463	0	-15	-99	0
ABBOTT STREET	0	0	726	0	0	544	0	0	43	0	0	501
4TH STREET	0	157	0	0	118	0	0	128	0	0	-10	0
3RD STREET	611	0	362	458	0	272	0	0	26	458	0	246
2ND STREET	398	0	0	298	0	0	385	0	0	-87	0	0
BROADWAY AVENUE	230	335	171	98	251	128	97	219	38	1	32	90
HAMPDEN AVENUE	902	0	0	677	0	0	128	0	0	549	0	0
DETENTION BASIN I-3	5,172	1,724	0	3,879	1,293	0	21	0	0	3,858	1,293	0
TOTALS:	10,633	2,702	1,259	7,900	2,026	944	3,136	810	107	4,764	1,216	837

EARTH EXCAVATION	14,594

FURNISHED EXCAVATION	-4,053
REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	4,053