



2/23/2009 11:52:45 AM  
 ps:\00files\000024\HUMBERT-Bridge\Plans\060-0308\gr-ders.dgn



**ELEVATION OF BEAM**  
(Showing reinforcement & dimensions)


\*3 spaces at 76 = 228  
 \*\*4- 20 mm  $\phi$  threaded dowel rods at 76 cts., Each Face.




**ELEVATION OF BEAM**  
(Showing Prestressing Steel)

INTERIOR BEAM REACTION TABLE	
	Abut. & Appr. Bent
$R_D$	(kN) 73
$R_{SD}$	(kN) 25
$R_L$	(kN) 149
Imp.	(kN) 45
$R$ (Total)	(kN) 292


DESIGNED	ADL
CHECKED	WLW
DRAWN	ADL/DGM
CHECKED	WLW




**PLAN AT ENDS OF BEAM**  
(Showing Inserts)



**BAR G1**




**BAR G2**



**BAR G4**

Note A:  
 Hex nuts (top and bottom) with lock washers (top). Only tighten sufficiently to compress lock washers.




**SECTION A-A**

**SECTION B-B**

INTERIOR BEAM MOMENT TABLE	
	0.5 Span
$I$	( $10^6 \text{ mm}^4$ ) 20,249
$I'$	( $10^6 \text{ mm}^4$ ) 81,557
$S_b$	( $10^3 \text{ mm}^3$ ) 51,867
$S_b'$	( $10^3 \text{ mm}^3$ ) 107,490
$S_t$	( $10^3 \text{ mm}^3$ ) 38,643
$S_t'$	( $10^3 \text{ mm}^3$ ) 525,268
$D$	(kN/m) 16.16
$M_D$	(kN·m) 166
$s_D$	(kN/m) 5.47
$M_{SD}$	(kN·m) 56
$M_L$	(kN·m) 256
$M$ (Imp)	(kN·m) 77

$I$  and  $I'$  are the moment of inertia and composite moment of inertia of the beam section.  
 $S_b$  and  $S_b'$  are the non-composite and composite section modulus for the bottom fiber of the prestressed beam.  
 $S_t$  and  $S_t'$  are the non-composite and composite section modulus for the top fiber of the prestressed beam.  
 $M_D$  is the moment due to dead loads on the non-composite prestressed beam.  
 $M_{SD}$  is the moment due to dead loads on the composite section.  
 $M_L$  is the moment due to live load on the composite section.  
 $M$  (Imp) is the moment due to live load impact on the composite section.



**SECTION C-C**

**\* BAR LIST**

Bar	No.	Size	Length (m)	Shape
$G_1$	25	#13	2.267	U
$G_2$	8	#13	1.733	U
$G_3$	3	#15	9.230	—
$G_4$	38	#10	1.244	△

\* For one beam only. (12 required)

**BILL OF MATERIAL**

Item	Unit	Total
Furnishing and Erecting Precast Prestressed Concrete I-Beams, 914 mm	m	111.7

**36" P.P.C. I-BEAM & DETAILS**  
 (EAST APPROACHES)  
 FAP RTE. 310 (IL RTE. 255) OVER  
 CH ROUTE 4 (HUMBERT ROAD)  
 SECTION 60-15HB-1  
 MADISON COUNTY  
 STATION 38+829.909  
 SN 060-0308 (NB) & 060-0309 (SB)

ROUTE NO.	SECTION	COUNTY	SHEET NO.	SHEET TOTAL
P.A.P. 310	*	MADISON	239	146

FED. ROAD DIST. NO. 7 ILLINOIS FED. AID PROJECT-  
 \* 60-15HB-1 CONTRACT NO. 76635

SHEET NO. 24  
 48 SHEETS