

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
70	60-10K-1, 60-10HB	MADISON	420	6
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

I000-1A

X711-2A

I000-1A

ILLINOIS DEPARTMENT OF TRANSPORTATION			TOTAL QUANTITIES	I-70 & FRONTAGE RD		I-70 & FRONTAGE RD		IL 162 e	IL 162 e	I-55/70		IL 162	
CODE NO	ITEM	UNIT		ROADWAY 100% FED	ROADWAY 100% FED	ROADWAY 100% FED	ROADWAY 100% FED	TRAFFIC SIGNALS 100% FED	TRAFFIC SIGNALS 100% FED	BRIDGE REPLACEMENT 100% FED	MSE WALLS 100% FED	SIGNING 100% FED	HIGHWAY LIGHTING 100% FED
40800020	BITUMINOUS MATERIALS (PRIME COAT)	TON	2.4	1.6			0.8						
40800030	AGGREGATE (PRIME COAT)	TON	3.8	2.6			1.2						
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	171	118			53						
42000506	PORTLAND CEMENT CONCRETE PAVEMENT 10 1/4" (JOINTED)	SQ YD	36474		23628	12846							
42000516	PORTLAND CEMENT CONCRETE PAVEMENT 10 3/4" (JOINTED)	SQ YD	7875			7875							
42001300	PROTECTIVE COAT	SQ YD	60864		35413	25451							
42001400	BRIDGE APPROACH PAVEMENT (SPECIAL)	SQ YD	1784		1016	768							
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	1305	1305									
44000100	PAVEMENT REMOVAL	SQ YD	62337	29336		20287	12714						
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	7476		7476								
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	5955	5387			568						
44000300	CURB REMOVAL	FOOT	537	499				38					
44000700	APPROACH SLAB REMOVAL	SQ YD	188				188						
44003100	MEDIAN REMOVAL	SQ FT	18316				18316						
44004000	PAVED DITCH REMOVAL	FOOT	181	181									
44004250	PAVED SHOULDER REMOVAL	SQ YD	14783	344	1288	11035	2116						
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	1460		1460								
48100500	AGGREGATE SHOULDERS, TYPE A 6"	SQ YD	3507		639	2672	196						
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	4874	4225	649								
48300505	PORTLAND CEMENT CONCRETE SHOULDERS 10 1/4"	SQ YD	10986			10698	288						
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1						1				
50104400	CONCRETE HEADWALL REMOVAL	EACH	3	1		2							
50105220	PIPE CULVERT REMOVAL	FOOT	579	298		239	42						
50157300	PROTECTIVE SHIELD	SQ YD	1146						1146				
50200100	STRUCTURE EXCAVATION	CU YD	401						401				
50300225	CONCRETE STRUCTURES	CU YD	1977			33			770	1174			
50300255	CONCRETE SUPERSTRUCTURE	CU YD	858						858				
50300260	BRIDGE DECK GROOVING	SQ YD	2935						2935				
50300300	PROTECTIVE COAT	SQ YD	5328						3456	1872			
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1						1				
50500505	STUD SHEAR CONNECTORS	EACH	16981						16981				

PLOT DATE = 2/18/2009
 FILE NAME = G:\pva\work\pva\mtdot\veplurcl\dm88415\p080830.dgn
 SHEET / IN.
 REFERENCE = #REF#