EAST FRONTAGE ROAD
STA. 13+00 TO 16+00

2' 12' 12' 12'

TEMPORARY PAVEMENT MARKING (TYP.)

TEMPORARY PAVEMENT, 9½"
(PAID FOR AS HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 9½")
(HOT-MIX ASPHALT BINDER COURSE, 7½")
(HOT-MIX ASPHALT SURFACE COURSE, 2")
(LIME MODIFIED SOIL, 12" MIN.)

EAST FRONTAGE ROAD
STA. 16+00 TO 34+30

2' 12' 12' 4' VARIES 24' TO 46'

TEMPORARY PAVEMENT MARKING (TYP.)

TEMPORARY PAVEMENT, 9½"
(PAID FOR AS HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 9½")
(HOT-MIX ASPHALT BINDER COURSE, 7½")
(HOT-MIX ASPHALT SURFACE COURSE, 2")
(LIME MODIFIED SOIL, 12" MIN.)

EAST FRONTAGE ROAD
STA. 35+13 TO 51+37

2' 12' 12' 4' VARIES 24' TO 40'

TEMPORARY PAVEMENT MARKING (TYP.)

TEMPORARY PAVEMENT, 11¼"
(PAID FOR AS HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 11¼")
(HOT-MIX ASPHALT BINDER COURSE, 9¼")
(HOT-MIX ASPHALT SURFACE COURSE, 2")
(LIME MODIFIED SOIL, 12" MIN.)

EXIST ℄

4' VARIES 11' TO 36' 4' 12' 12'

TEMPORARY PAVEMENT MARKING (TYP.)

WEST FRONTAGE ROAD
11+17 TO 15+00

TEMPORARY PAVEMENT, 9½"
(PAID FOR AS HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 9½")
(HOT-MIX ASPHALT BINDER COURSE, 7½")
(HOT-MIX ASPHALT SURFACE COURSE, 2")
(LIME MODIFIED SOIL, 12" MIN.)

EXIST ℄

VARIES 36' TO 70' 12' 12' 2'

TEMPORARY PAVEMENT MARKING (TYP.)

1:3

WEST FRONTAGE ROAD
STA. 15+00 TO 19+13

TEMPORARY PAVEMENT, 9½"
(PAID FOR AS HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 9½")
(HOT-MIX ASPHALT BINDER COURSE, 7½")
(HOT-MIX ASPHALT SURFACE COURSE, 2")
(LIME MODIFIED SOIL, 12" MIN.)

EXIST ℄

VARIES 12' TO 53' 12' 12' 2'

TEMPORARY PAVEMENT MARKING (TYP.)

1:3

WEST FRONTAGE ROAD
STA. 20+00 TO 26+00

TEMPORARY PAVEMENT, 10½"
(PAID FOR AS HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 10½")
(HOT-MIX ASPHALT BINDER COURSE, 8½")
(HOT-MIX ASPHALT SURFACE COURSE, 2")
(LIME MODIFIED SOIL, 12" MIN.)

12' 12'

TEMPORARY PAVEMENT MARKING (TYP.)

TEMPORARY PAVEMENT, 10½"
(PAID FOR AS HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 10½")
(HOT-MIX ASPHALT BINDER COURSE, 8½")
(HOT-MIX ASPHALT SURFACE COURSE, 2")
(LIME MODIFIED SOIL, 12" MIN.)

WEST FRONTAGE ROAD
STA. 26+00 TO 27+68

ILLINOIS DEPARTMENT OF TRANSPORTATION

MAINTENANCE OF TRAFFIC - 2
TYPICAL SECTIONS STAGE I
FRONTAGE ROADS

FAI ROUTE 70
SECTION 60-10K-1, 60-10HB
MADISON COUNTY

REVISIONS	
NAME	DATE

DRAWN BY: GRH

PLOT DATE: *DATE-TIME*

PLAN

SURVEYED
PLOTTED
ALIGNMENT CHECKED
R. OF WAY CHECKED
CADD FILE NAME

NOTE BOOK NO.

BY
DATE