

# SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE			SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		X071-2A 20% STATE 80% FED			CODE NO	ITEM	UNIT		X071-2A 20% STATE 80% FED		
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	348	348		42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SQ YD	43	43			
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	104	104		44000100	PAVEMENT REMOVAL	SQ YD	387	387			
20200100	EARTH EXCAVATION	CU YD	635	635		44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	35	35			
20300100	CHANNEL EXCAVATION	CU YD	755	755		44000400	GUTTER REMOVAL	FOOT	155	155			
20400800	FURNISHED EXCAVATION	CU YD	315	315		44004250	PAVED SHOULDER REMOVAL	SQ YD	179	179			
20700400	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	98	98		50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1	1			
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	400	400		50105220	PIPE CULVERT REMOVAL	FOOT	111	111			
25000200	SEEDING, CLASS 2	ACRE	0.9	0.9		50200100	STRUCTURE EXCAVATION	CU YD	142	142			
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	90	90		50300100	FLOOR DRAINS	EACH	8	8			
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	90	90		50300225	CONCRETE STRUCTURES	CU YD	32	32			
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	90	90		50300254	RUBBED FINISH	SQ FT	32	32			
25100115	MULCH, METHOD 2	ACRE	2.2	2.2		50300255	CONCRETE SUPERSTRUCTURE	CU YD	91.9	91.9			
25200100	SODDING	SQ YD	400	400		50300260	BRIDGE DECK GROOVING	SQ YD	210	210			
25200200	SUPPLEMENTAL WATERING	UNIT	1	1		50300280	CONCRETE ENCASEMENT	CU YD	4.2	4.2			
28000255	TEMPORARY EROSION CONTROL SEEDING	ACRE	1.3	1.3		50300300	PROTECTIVE COAT	SQ YD	277	277			
28100107	STONE RIPRAP, CLASS A4	SQ YD	544	544		50800515	BAR SPLICERS	EACH	282	282			
28100205	STONE RIPRAP, CLASS A3	TON	266	266		50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1	1			
28200200	FILTER FABRIC	SQ YD	1169	1169		50500505	STUD SHEAR CONNECTORS	EACH	1116	1116			
35100700	AGGREGATE BASE COURSE, TYPE A B"	SQ YD	353	353		50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	24210	24210			
35600716	HOT-MIX ASPHALT BASE COURSE WIDENING, 10"	SQ YD	896	896		51201600	FURNISHING STEEL PILES HP12X53	FOOT	660	660			
35800100	PREPARATION OF BASE	SQ YD	214	214		51202305	DRIVING PILES	FOOT	660	660			
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	353	353		51204650	PILE SHOES	EACH	12	12			
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	174	174		51205200	TEMPORARY SHEET PILING	SQ FT	866	866			
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	0.5	0.5		51500100	NAME PLATES	EACH	1	1			
40600300	AGGREGATE (PRIME COAT)	TON	2	2		52100520	ANCHOR BOLTS, 1"	EACH	24	24			
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	45	45		54200637	PIPE CULVERTS, TYPE 1, CORRUGATED STEEL OR ALUMINUM CULVERT PIPE 12"	FOOT	47	47			
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	187	187		5421A018	PIPE CULVERTS, CLASS A, TYPE 1 18" (TEMPORARY)	FOOT	191	191			
40600990	TEMPORARY RAMP	SQ YD	31	31		5421A036	PIPE CULVERTS, CLASS A, TYPE 1 36" (TEMPORARY)	FOOT	296	296			
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	677	677		542D0223	PIPE CULVERTS, CLASS D, TYPE 1 18"	FOOT	42	42			
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	137	137		59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	56	56			
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	14	14		60109580	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	170	170			
42001165	BRIDGE APPROACH PAVEMENT	SQ YD	214	214		60600095	CLASS SI CONCRETE (OUTLET)	CU YD	1	1			
<del>42001200</del>	<del>PAVEMENT FABRIC</del>	<del>SQ YD</del>	<del>214</del>	<del>214</del>		60602800	CONCRETE GUTTER, TYPE B	FOOT	155	155			
42001300	PROTECTIVE COAT	SQ YD	494	491		*63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	412.5	412.5			

\*SPECIALTY ITEMS

FILE NAME =	USER NAME = manntm	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
c:\pwork\pwork\manntm\dms51935\p1n82	206a.dgn	DRAWN -	REVISED -			325	3BR-2	JERSEY	90	3	
PLOT SCALE = 50,0000' / IN.		CHECKED -	REVISED -			CONTRACT NO. 76B01					
PLOT DATE = 12/11/2008		DATE -	REVISED -			SCALE:	SHEET NO. 1 OF 2 SHEETS	STA.	TO STA.	FED. ROAD DIST. NO. 8 ILLINOIS FED. AID PROJECT	

Rev.