

TREE REMOVAL SCHEDULE

STATIONING	LT/RT	OFFSET	6 TO 15 UNITS IN DIAMETER UNIT	OVER 15 UNITS IN DIAMETER UNIT	COMMENTS
117+63.1		29.3 RT	8		
117+77.5		28.7 RT	8		
117+80.5		28.9 RT	10		
117+88.7		29.3 RT	10		
118+00.0		28.6 RT	8		
118+05.2		29.5 RT	14		
118+14.8		30.0 LT	10		
118+23.9		28.5 RT	8		
118+62.7		31.5 RT	6		
118+90.8		27.9 RT	12		
118+89.6		31.5 LT	6		
119+12.6		43.1 LT	6		
119+18.2		31.0 RT	12		
119+18.6		42.8 LT	14		
119+23.7		32.3 LT	14		
119+25.2		41.9 LT		36	
119+32.3		43.0 LT	12		
119+35.2		43.0 RT	10		
119+36.0		34.5 RT	8		
119+36.8		43.0 LT	6		
119+37.9		36.7 RT		20	
119+41.9		30.5 RT	6		
119+44.8		40.0 RT	8		
119+44.8		40.3 RT	6		
119+50.0		32.9 RT	24		3 @ 8" DIA
119+52.3		38.2 LT	6		
119+56.9		38.0 RT	12		
119+58.8		28.9 RT	6		
119+60.3		35.4 LT	8		
119+60.3		35.7 LT	6		
119+62.4		32.4 RT	20		2 @ 10' DIA
119+69.7		35.1 LT		30	
119+69.7		35.5 LT	6		
119+88.0		34.7 RT	6		
119+90.3		95.7 LT		18	
119+91.7		41.4 RT	6		
119+92.4		50.0 LT	6		
120+02.2		32.7 RT	8		
120+04.1		31.9 RT	8		
120+11.1		38.9 RT	10		
120+17.1		39.0 RT	6		
120+38.8		37.3 RT	8		
TOTAL			348	104	

HAULROAD EARTHWORK SCHEDULE

STATIONING	EARTH EXCAVATION CUBIC YARD	EARTH EX ADJUSTED FOR SHRINKAGE CUBIC YARD	EMBANKMENT CUBIC YARD	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-) CUBIC YARD
0+40 to 1+80	46.15	34.61	82.20	-47.58
2+20 to 3+40	182.02	170.58	5.23	165.35
TOTALS	228.17	205.20	87.43	117.77

PAVEMENT MARKING SCHEDULE

STATION	THERMOPLASTIC PAVEMENT MARKING LINE-4" (FOOT)		POLYUREA PAVEMENT MARKING LINE-4" (FOOT)		SHORT TERM PAVEMENT MARKING (FOOT)	RAISED RELECTIVE PAVEMENT MARKERS (EACH)	RAISED RELECTIVE PAVT. MRKS. (BRIDGE) (EACH)	RAISED RELECTIVE PAVT. MRK. REMOVAL (EACH)	PAVEMENT MARKING REMOVAL (SQ FT)	WORK ZONE PAVEMENT MRK. REM. (SQ FT)	
	SOLID WHITE	SOLID YELLOW	SOLID WHITE	SOLID YELLOW							
	TO	TO	TO	TO							
115+89.50	TO	117+00.00	221	221		11.1	1	1	82.9	2.8	
117+00.00	TO	119+10.50	421	421		21.1	3	3	157.9	5.3	
119+10.50	TO	120+45.50			270	13.5		2	101.3	3.4	
120+45.50	TO	123+00.00	509	509		25.5	3	3	190.9	6.4	
123+00.00	TO	124+56.50	313	313		15.7	2	2	117.4	3.9	
SUBTOTAL			1464	1464	270	86.9	9	2	11	650.4	22
TOTAL			2928		540	87	9	2	11	651	21.7

CHANNEL EARTHWORK SCHEDULE

STA	to	STA	UNADJUSTED CHANNEL EXCAVATION (CU YD)	CHANNEL EXCAVATION ADJUSTED FOR 25% SHINKAGE (CU YD)	EMBANKMENT (CU YD)	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-) (CU YD)
+0.00	to	+10.00	56.5	42.4	0.0	42.4
+10.00	to	+20.00	61.5	46.1	0	46.1
+20.00	to	+29.47	68.4	51.3	0	51.3
+29.47	to	+39.47	90.9	68.2	0	68.2
+39.47	to	+47.07	82.4	61.8	0	61.8
+47.07	to	+57.07	109.7	82.3	0	82.3
+57.07	to	+63.11	61.5	46.1	0	46.1
+63.11	to	+70.00	59.7	44.8	0	44.8
+70.00	to	+80.00	71.3	53.5	0	53.5
+80.00	to	+90.00	52.1	39.1	0	39.1
+90.00	to	+100.00	30	22.5	0	22.5
+100.00	to	+110.00	11.8	8.9	0	8.9
TOTAL =			755.8	567.0	0.0	567.0
ROUNDED TOTAL =			755	565	0	565

LONE STAR ROAD EARTHWORK SCHEDULE

STA	to	STA	UNADJUSTED EXCAVATION (CU YD)	EXCAVATION ADJUSTED FOR 25% SHINKAGE (CU YD)	EMBANKMENT (CU YD)	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-) (CU YD)
+0.00	to	+16.03	0.0	0.0	0.0	0.0
+16.03	to	+25.00	2	1.5	0.8	0.7
+25.00	to	+50.00	12.4	9.3	12.8	-3.5
+50.00	to	+75.00	13.3	10	12.2	-2.2
+75.00	to	+100.00	13	9.8	3.2	6.6
+100.00	to	+110.00	2.6	2	0.6	1.4
+110.00	to	+120.00	0	0	0	0
TOTAL =			43.3	32.6	29.6	3.0
ROUNDED TOTAL =			45	35	30	5

MAINLINE EARTHWORK SCHEDULE

STA	to	STA	UNADJUSTED EXCAVATION (CU YD)	EXCAVATION ADJUSTED FOR 25% SHINKAGE (CU YD)	EMBANKMENT (CU YD)	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-) (CU YD)
115+50.00	to	116+00.00	0.0	0.0	5.3	-5.3
116+00.00	to	116+50.00	9.3	7	31.2	-24.2
116+50.00	to	117+00.00	11.1	8.3	46.1	-37.8
117+00.00	to	117+50.00	11.4	8.6	48.6	-40
117+50.00	to	118+00.00	10.5	7.9	56.3	-48.4
118+00.00	to	118+50.00	8.7	6.5	56.1	-49.6
118+50.00	to	119+00.00	7.6	0	74.6	-74.6
119+00.00	to	119+47.75	3.7	2.8	44.3	-41.5
119+47.75	to	120+09.50	0	0	0	0
120+09.50	to	120+25.00	5.9	4.4	11.9	-7.5
120+25.00	to	121+00.00	53.3	40	90.9	-45.9
121+00.00	to	121+50.00	31.6	23.7	25.5	-1.8
121+50.00	to	122+00.00	25.7	19.3	12.7	6.6
122+00.00	to	122+50.00	22.4	0	9.4	-9.4
122+50.00	to	123+00.00	19.6	14.7	4.6	10.1
123+00.00	to	123+50.00	0	0	1.6	-1.6
123+50.00	to	124+00.00	37.4	28.1	0.3	27.8
124+00.00	to	124+50.00	30.7	23	0	23
124+50.00	to	125+00.00	9.1	6.8	0	6.8
TOTAL =			298.0	201.1	514.4	-313.3
ROUNDED TOTAL =			300	200	515	-315

TEMPORARY ENTRANCE EARTHWORK SCHEDULE

STA	to	STA	UNADJUSTED EXCAVATION (CU YD)	EXCAVATION ADJUSTED FOR 25% SHINKAGE (CU YD)	EMBANKMENT (CU YD)	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-) (CU YD)
+25.00	to	+50.00	12.3	9.2	3.6	5.6
+50.00	to	+75.00	11.4	8.6	3.6	5
+75.00	to	+100.00	12.4	9.3	2.5	6.8
+100.00	to	+109.21	4.2	3.2	0.2	3
+109.21	to	+129.83	5.7	4.3	1.5	2.8
+129.83	to	+150.00	4	3	2.9	0.1
+150.00	to	+175.00	5.3	0	2.8	-2.8
+175.00	to	+200.00	4.6	3.5	0.8	2.7
+200.00	to	+201.00	0	0	0	0
+201.00	to	+210.00	0	0	0	0
TOTAL =			59.9	41.1	17.9	23.2
ROUNDED TOTAL =			60	40	20	20