

042004L76B01.08.TSEL.DGN AUG. 26, 2008

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

BEAM #4

Location	Station	Offset from Ctrline	Theoretical Grade Elevations	Theoretical Grade Elevations Adjusted for Dead Load Deflection
Bk. W. Abut.	119+46.50	2.92	452.64	452.64
⊙ Brg. W. Abut.	119+47.75	2.92	452.64	452.64
A	119+57.75	2.92	452.66	452.70
B	119+67.75	2.92	452.66	452.75
C	119+77.75	2.92	452.67	452.76
D	119+87.75	2.92	452.67	452.75
E	119+97.75	2.92	452.67	452.71
⊙ Brg. E. Abut.	120+08.25	2.92	452.66	452.66
Bk. E. Abut.	120+09.50	2.92	452.66	452.66

BEAM #5

Location	Station	Offset from Ctrline	Theoretical Grade Elevations	Theoretical Grade Elevations Adjusted for Dead Load Deflection
Bk. W. Abut.	119+46.50	8.75	452.55	452.55
⊙ Brg. W. Abut.	119+47.75	8.75	452.55	452.55
A	119+57.75	8.75	452.57	452.61
B	119+67.75	8.75	452.57	452.65
C	119+77.75	8.75	452.58	452.67
D	119+87.75	8.75	452.58	452.66
E	119+97.75	8.75	452.57	452.62
⊙ Brg. E. Abut.	120+08.25	8.75	452.57	452.57
Bk. E. Abut.	120+09.50	8.75	452.57	452.57

BEAM #6

Location	Station	Offset from Ctrline	Theoretical Grade Elevations	Theoretical Grade Elevations Adjusted for Dead Load Deflection
Bk. W. Abut.	119+46.50	14.58	452.45	452.45
⊙ Brg. W. Abut.	119+47.75	14.58	452.45	452.45
A	119+57.75	14.58	452.46	452.51
B	119+67.75	14.58	452.47	452.55
C	119+77.75	14.58	452.47	452.57
D	119+87.75	14.58	452.47	452.56
E	119+97.75	14.58	452.47	452.52
⊙ Brg. E. Abut.	120+08.25	14.58	452.46	452.46
Bk. E. Abut.	120+09.50	14.58	452.46	452.46

DESIGNED	B.G.H.
CHECKED	L.D.G.
DRAWN	K.H.L.
CHECKED	B.G.H.

Notes:
1. Elevations are at Top of Concrete.
2. See Sheet 6 for elevation locations.

TOP OF SLAB ELEVATIONS

SHEET NO. 8	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	325	3BR-2	JERSEY	96	49
21 SHEETS	S.N. 042-0041		CONTRACT NO. 76B01		
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT					

H.M. & G. NO. 6020.III