

HOT-MIX ASPHALT BASE COURSE WIDENING, 10"				
SHEET	STATION	STATION	LOCATION	SQ YD
10	468+06.00	468+60.00	IL ROUTE 242, RT.	26
11	471+39.90	473+00.00	IL ROUTE 242, LT.	53
11	471+68.18	473+00.00	IL ROUTE 242, RT.	42
TOTAL				121

BRIDGE APPROACH PAVEMENT				
SHEET	STATION	STATION	LOCATION	SQ YD
8	469+87.00	470+17.00	IL ROUTE 242	111
9	471+35.00	471+65.00	IL ROUTE 242	111
TOTAL				222

BRIDGE APPROACH PAVEMENT CONNECTOR (RIGID)				
SHEET	STATION	STATION	LOCATION	SQ YD
8	469+78.08	469+87.00	IL ROUTE 242	33
9	471+65.00	471+73.92	IL ROUTE 242	33
TOTAL				66

PAVEMENT REMOVAL				
SHEET	STATION	STATION	LOCATION	SQ YD
8	469+78	470+14	IL ROUTE 242	129
9	471+40	471+74	IL ROUTE 242	127
TOTAL				256

HOT-MIX ASPHALT SHOULDERS, 8"				
SHEET	STATION	STATION	LOCATION	SQ YD
8	469+17.40	470+20.30	IL ROUTE 242, LT.	35
8	469+10.80	470+14.10	IL ROUTE 242, RT.	35
9	471+39.90	474+18.00	IL ROUTE 242, LT.	131
9	471+31.70	473+13.10	IL ROUTE 242, RT.	64
TOTAL				265

BRIDGE APPROACH PAVEMENT REMOVAL				
SHEET	STATION	STATION	LOCATION	SQ YD
8	470+14	470+33	IL ROUTE 242	66
9	471+20	471+40	IL ROUTE 242	68
TOTAL				134

STEEL RAILING (TEMPORARY)				
SHEET	STATION	STATION	LOCATION	FOOT
10-11	469+77	471+76	IL ROUTE 242	199
TOTAL				199

PIPE CULVERT, CLASS D, TYPE1 18"				
SHEET	STATION	STATION	LOCATION	FOOT
8	470+32	470+38	IL ROUTE 242, RT	6
TOTAL				6

ENGINEER'S FIELD OFFICE, TYPE A		
TOTAL		CAL MO
	7	

MOBILIZATION		
TOTAL		L SUM
	1	

TRAFFIC BARRIER TERMINAL, TYPE 6				
SHEET	STATION	STATION	LOCATION	EACH
8	469+76.77	470+22.42	IL ROUTE 242, LT.	1
8	469+70.93	470+16.58	IL ROUTE 242, RT.	1
9	471+35.42	471+81.07	IL ROUTE 242, LT.	1
9	471+29.58	471+75.23	IL ROUTE 242, RT.	1
TOTAL				4

TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT				
SHEET	STATION	STATION	LOCATION	EACH
8	469+26.77	469+76.77	IL ROUTE 242, LT.	1
8	469+20.93	469+70.93	IL ROUTE 242, RT.	1
9	473+56.07	474+06.07	IL ROUTE 242, LT.	1
9	472+50.23	473+00.23	IL ROUTE 242, RT.	1
TOTAL				4

STEEL PLATE BEAM GUARD RAIL, TYPE A				
SHEET	STATION	STATION	LOCATION	FOOT
9	471+81.07	473+56.07	IL ROUTE 242, LT.	175
9	471+75.23	472+50.23	IL ROUTE 242, RT.	75
TOTAL				250

TERMINAL MARKER - DIRECT APPLIED				
SHEET	STATION	STATION	LOCATION	EACH
8	469+26.77		IL ROUTE 242, LT.	1
8	469+20.93		IL ROUTE 242, RT.	1
9	473+56.07		IL ROUTE 242, LT.	1
9	471+75.23		IL ROUTE 242, RT.	1
TOTAL				4

STEEL PLATE BEAM GUARD RAIL REMOVAL, TYPE A				
SHEET	STATION	STATION	LOCATION	FOOT
8	469+39	470+02	IL ROUTE 242, LT.	63
8	469+37	470+00	IL ROUTE 242, RT.	63
9	471+53	472+16	IL ROUTE 242, LT.	63
9	471+53	472+16	IL ROUTE 242, RT.	63
TOTAL				252

REMOVAL AND REINSTALLATION OF EXISTING TRAFFIC BARRIER TERMINAL, TYPE 6				
SHEET	STATION	STATION	LOCATION	EACH
10	467+70 +/-	468+13 +/-	IL ROUTE 242, RT.	1
TOTAL				1

REMOVE AND RE-ERECT TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL, TANGENT				
SHEET	STATION	STATION	LOCATION	EACH
10	468+13 +/-	468+63 +/-	IL ROUTE 242, RT.	1
TOTAL				1

GUARDRAIL MARKERS, TYPE B				
SHEET	STATION	STATION	LOCATION	EACH
8	469+26.77	470+22.42	IL ROUTE 242, LT.	1
8	469+20.93	470+16.58	IL ROUTE 242, RT.	1
9	471+35.42	474+06.07	IL ROUTE 242, LT.	3
9	471+29.58	472+25.23	IL ROUTE 242, RT.	1
TOTAL				6

BARRIER WALL MARKER, TYPE B				
SHEET	STATION	STATION	LOCATION	EACH
8-9	470+22.42	471+35.42	IL ROUTE 242, LT.	2
8-9	470+16.58	471+29.58	IL ROUTE 242, RT.	2
TOTAL				4

IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW) TEST LEVEL 3		
TOTAL		EACH
	2	

IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE, NARROW) TEST LEVEL 3		
TOTAL		EACH
	2	

TRAFFIC CONTROL AND PROTECTION, STANDARD 701326		
TOTAL		L SUM
	1	

TRAFFIC CONTROL AND PROTECTION, STANDARD 701321		
TOTAL		EACH
	1	

TRAFFIC CONTROL AND PROTECTION, STANDARD 701201		
TOTAL		L SUM
	1	

TEMPORARY BRIDGE TRAFFIC SIGNALS		
TOTAL		EACH
	1	

TEMPORARY CONCRETE BARRIER		
TOTAL		FOOT
	417	

RELOCATE TEMPORARY CONCRETE BARRIER		
TOTAL		FOOT
	242	

CHANGEABLE MESSAGE SIGN		
TOTAL		CAL MO
	14	

PAINT PAVEMENT MARKING - LINE 4"					
SHEET	STATION	STATION	LOCATION	SOLID WHITE	INTERMITTENT YELLOW
8-9	468+48	473+04	IL ROUTE 242, LT.	456	
8-9	466+86	474+60	IL ROUTE 242		194
8-9	468+48	473+04	IL ROUTE 242, RT.	456	
TOTAL				912	194

PAVEMENT MARKING REMOVAL					
SHEET	STATION	STATION	LOCATION	SOLID WHITE	INTERMITTENT YELLOW
10	468+48	471+00	IL ROUTE 242, LT.	252	
10	466+86	469+34	IL ROUTE 242		62
11	471+00	473+04	IL ROUTE 242, LT.	204	
11	472+96	474+22	IL ROUTE 242		32
12	468+48	469+79	IL ROUTE 242, RT.	131	
13	474+22	474+60	IL ROUTE 242		10
13	471+69	473+04	IL ROUTE 242, RT.	135	
TOTAL				722	104

FILE NAME =
d978016-sht-schedu1e01.dgn

USER NAME = rossr1

DESIGNED - APF

REVISED -

DRAWN - APF

REVISED -

CHECKED - RSB

REVISED -

PLOT DATE = 01/19/2009

DATE = 1/15/2009

REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SHEET NO. 1 OF 2 SHEETS STA. TO STA.

F.A.
RTE.
776

SECTION
(102)B-1

COUNTY
HAMILTON

TOTAL SHEETS
53

SHEET NO.
6

CONTRACT NO. 78016

FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT