

REMOVAL SCHEDULE

LOCATION STATION TO STATION	LENGTH (FT)	PAVEMENT WIDTH (FT)	HOT-MIX ASPHALT SURFACE REMOVAL 1 1/2" (SQ YD)	MEDIAN REMOVAL (SPECIAL) (SQ FT)	REMARKS
IL 146					
0 + 21 to 1 + 00	79		310		LANE WIDENING AND SEPARATION AT JONESBORO SQUARE
1 + 00 to 10 + 98	998	22.5	2495		
10 + 98 to 20 + 05	907	VAR.	2590		VARIABLE WIDTH (23.8 TO 28.0)
20 + 05 to 21 + 05	100	VAR.	333		VAR. WIDTH (25.0 TO 35.0), BEGIN TAPER FOR THIRD LANE (STA. 20+05 RT)
21 + 05 to 24 + 80	375	23	958		OMIT CONCRETE PAVEMENT IN RT LANE
24 + 80 to 40 + 01	1521	33	5577		
40 + 01 to 43 + 25	324	VAR.	1462		VARIABLE WIDTH (34.0 TO 42.6), WIDENING AT HIGH SCHOOL
43 + 25 to 48 + 59	534				OMISSION AT HIGH SCHOOL
48 + 59 to 59 + 33	1074	32.33	3858		
59 + 33 to 59 + 49	16	VAR.	66		VARIABLE WIDTH (32.33 TO 42.33), WIDENING AT JEFFERSON ST.
59 + 49 to 70 + 84.5	1135.5	42.33	5341		
70 + 84.5 to 70 + 95	10.5				OMISSION AT RAILROAD TRACKS
70 + 95 to 71 + 14	19	42.33	89		WHITE TOPPING BEGINS AT STA. 71+14
71 + 14 to 73 + 31					OMISSION AT WHITE TOPPING
73 + 31 to 89 + 65	1634	36	6536		
89 + 65 to 92 + 17	252	24.5	686		CONCRETE PAVEMENT IN LT. LANE
92 + 17 to 104 + 49	1232	36	4928		BEGIN PAVEMENT WIDTH TAPER (STA. 104+49 LT.)
104 + 49 to 104 + 66	17	VAR.	70		BEGIN PAVEMENT WIDTH TAPER (STA. 104+66 RT.)
104 + 66 to 106 + 64	198	VAR.	1078		
106 + 64 to 127 + 30	2066	62	14232		MEDIAN BEGINS AT 127+30=21+54.74
110 + 88 to 113 + 92		VAR.	364		RT. TURN LANE AT SPRINGFIELD AVE.
21 + 54.74 to 26 + 20.39	465.65	VAR.	2797		MEDIAN ENDS AT 26+20.39
26 + 20.39 to 27 + 19.97	99.58	66	730		MEDIAN BEGINS STA. 27+19.97
27 + 19.97 to 32 + 29.36	509.45	VAR.	3149		MEDIAN ENDS STA. 32+29.36
28 + 64 to 32 + 29.36	365.36			6576	
TOTALS			57651	6576	