

SCHEDULE OF QUANTITIES - CONT.

ROUTE F.A.S. 60	SECTION 07-00172-00-BR	COUNTY STEPHENSON	SHEETS 31	SHEET 3
FED. ROAD DIST. NO. 7	BILLINGS	FED. AID PROJECT -	BRS-60(2)	

<b>BITUMINOUS MATERIALS (PRIME COAT)</b>		
LOCATION	GALLON	REMARKS
STA. 379+50-380+10.80	55	TAPER, 0.375 GAL/SY
STA. 380+10.80-382+54.25	223	0.375 GAL/SY
STA. 384+89.75-389+74.86	445	0.375 GAL/SY
STA. 389+74.86-390+00	23	TAPER, 0.375 GAL/SY
P.E.R. 388+05	49	0.375 GAL/SY
TOTAL	795 GALLON	
<b>BRIDGE APPROACH PAVEMENT</b>		
LOCATION	SQ. YD.	REMARKS
STA. 382+54.25-382+84.25	100	
STA. 384+59.75-384+89.75	100	
TOTAL	200 SQ. YD.	
<b>AGGREGATE SHOULDERS, TYPE B</b>		
LOCATION	TON	REMARKS
RT. STA. 379+50-379+58	1	TAPER 6" COMPACTED
RT. STA. 379+58-380+22.5	11	6" COMPACTED
RT. STA. 386+88-387+88	15	6" COMPACTED
RT. STA. 388+22-389+83	24	6" COMPACTED
RT. STA. 389+83-390+00	2	TAPER 6" COMPACTED
LT. STA. 379+50-380+68	2	TAPER 6" COMPACTED
LT. STA. 379+68-380+84.50	18	6" COMPACTED
LT. STA. 387+38-389+87	38	6" COMPACTED
LT. STA. 389+87-390+00	2	TAPER 6" COMPACTED
TOTAL	113 TON	
<b>PIPE CULVERTS, TYPE 1, CORRUGATED STEEL CULVERT PIPE 15"</b>		
LOCATION	FOOT	REMARKS
F. E. R. 388+05.00	53	
TOTAL	53 FOOT	
<b>PIPE CULVERTS, TYPE 1, CORRUGATED STEEL, EQUIVALENT ROUND - SIZE 54"</b>		
LOCATION	FOOT	REMARKS
F. E. L. 380+98.50	47	
TOTAL	47 FOOT	
<b>STEEL END SECTIONS 15"</b>		
LOCATION	EACH	REMARKS
F. E. R. 388+05.00	2	
TOTAL	2 EACH	
<b>STEEL END SECTIONS, EQUIVALENT ROUND-SIZE 54"</b>		
LOCATION	EACH	REMARKS
F. E. L. 380+98.50	2	
TOTAL	2 EACH	
<b>STEEL PLATE BEAM GUARDRAIL, TYPE A</b>		
LOCATION	FOOT	REMARKS
SOUTHWEST QUADRANT	137.5	
SOUTHEAST QUADRANT	100	
NORTHWEST QUADRANT	75	
NORTHEAST QUADRANT	150	
TOTAL	462.5 FOOT	
<b>TRAFFIC BARRIER TERMINAL, TYPE 6A</b>		
LOCATION	EACH	REMARKS
SOUTHWEST QUADRANT	1	
SOUTHEAST QUADRANT	1	
NORTHWEST QUADRANT	1	
NORTHEAST QUADRANT	1	
TOTAL	4 EACH	

<b>TRAFFIC BARRIER TERMINAL, TYPE 1, SPECIAL (TANGENT)</b>		
LOCATION	EACH	REMARKS
SOUTHWEST QUADRANT	1	
SOUTHEAST QUADRANT	1	
NORTHWEST QUADRANT	1	
NORTHEAST QUADRANT	1	
TOTAL	4 EACH	
<b>GUARDRAIL REMOVAL</b>		
LOCATION	FOOT	REMARKS
SOUTHWEST QUADRANT	51	
SOUTHEAST QUADRANT	26	
NORTHWEST QUADRANT	51	
NORTHEAST QUADRANT	50	
TOTAL	178 FOOT	
<b>SHORT TERM PAVEMENT MARKING</b>		
LOCATION	FOOT	REMARKS
RT. STA. 379+50-390+00	44	WHITE (4' @ 45°-100 CTS.)
STA. 379+50-390+00	96	YELLOW (4' -40' SP)
LT. STA. 379+50-390+00	44	WHITE (4' @ 45°-100 CTS.)
TOTAL	184 FOOT	
<b>WORK ZONE PAVEMENT MARKING REMOVAL</b>		
LOCATION	SQ. FT.	REMARKS
RT. STA. 379+50-390+00	15	4" WIDE
STA. 379+50-390+00	32	4" WIDE
LT. STA. 379+50-390+00	15	4" WIDE
TOTAL	62 SQ. FT.	
<b>PAINT PAVEMENT MARKING - LINE 4"</b>		
LOCATION	FOOT	REMARKS
RT. STA. 379+50-390+00	1,050	WHITE EDGE LINE
STA. 379+50-390+00	270	YELLOW (10' -30' SP)
LT. STA. 379+50-390+00	1,050	WHITE EDGE LINE
TOTAL	2,370 FOOT	
<b>GUARDRAIL MARKERS, TYPE A</b>		
LOCATION	EACH	REMARKS
RT. STA. 381+03-386+03	21	
LT. STA. 381+66-386+53	20	
TOTAL	41 EACH	
<b>TERMINAL MARKER - DIRECT APPLIED</b>		
LOCATION	EACH	REMARKS
SOUTHWEST QUADRANT	1	
SOUTHEAST QUADRANT	1	
NORTHWEST QUADRANT	1	
NORTHEAST QUADRANT	1	
TOTAL	4 EACH	

SCHEDULES  
 CEDARVILLE ROAD (FAS 60) OVER RICHLAND CREEK  
 STA. 383+72 (S.N. 089-3282)  
 SECTION 07-00172-00-BR  
 STEPHENSON COUNTY  
 WHA #1106D07